

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05190305	Call Order: 003	Proposal: E5Z68	District:05
Counties:	BREVARD			
Road Name:	SR 520 EB & WB OVER INDIAN RIVER BRIDGE # 700061 & 700137			
Limits:	70100000			
Project(s):	44096915201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.888 Miles	Contract Days:	180	
Total Bridge Length:	0.888 Miles	Letting Date:	03/05/19	
Total Proposal Length:	1.776 Miles	Contract Execution Days:		
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60	

Proposal Budget Estimate: \$2,180,952.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of bulkhead cap rehabilitation, lateral bracing replacements, and bearing retrofits at SR 520 over Indian River (Bridge Nos. 700061 and 700137) in Brevard County.

PREQUALIFICATION REQUIRED

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: E5Z68

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	19.200
	0400-147-	COMPOSITE NEOPRENE PADS	CF	16.100
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	3,072.000
	0460- 1- 15	STRUCTURAL STEEL - REHABILITATION, MISCELLANEOUS	LB	36,034.000
	0561- 2-	COATING EXISTING STRUCTURAL STEEL	SF	700.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44096915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44096915201)	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	200.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	1,200.000
	0110- 1- 1	CLEARING & GRUBBING (44096915201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	204.000
	0110- 73-	REMOVE EXISTING BULKHEAD	LF	864.000
	0285-706-	OPTIONAL BASE, BASE GROUP 06	SY	74.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	196.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	22.500
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	1.900
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL	CY	2.400
	0400- 4- 8	CONC CLASS IV, BULKHEAD	CY	96.000
	0415- 10- 5	FIBER REINFORCED POLYMER BARS, #5 BAR	LF	13,806.000
	0515- 2-500	PEDESTRIAN / BICYCLE RAILING, RELOCATE	LF	68.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	300.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	60.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	136.000
	0530- 1-	RIPRAP, SAND-CEMENT	CY	11.600
	0536- 1- 0	GUARDRAIL -ROADWAY, GENERAL/LOW SPEED TL-2	LF	194.000
	0536- 73-	GUARDRAIL REMOVAL	LF	194.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	245.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44096915201)	LS	1.000