Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05190904 Call Order: 001 Proposal: E5V10 District:05

Counties: ORANGE

Road Name: Drainage Repair

Limits: Midpoint

Project(s): 44192817202(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	09/04/19
Total Proposal Length:	0.000 Miles	Contract Execution Days:	
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: $351,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID: E5V10
Project No: 441928-1-72-02
Fiscal Year: 2020

Counties: Orange
Contract Calendar Days: 90
Lead Time: 14

This is a Maintenance Pay Item Project.

INTENT AND SCOPE:

The work under this Contract consists of desilting of pipes, providing color video before and after improvements, and lining storm drains on SR 423 in Orange County in accordance with Contract documents.

EXPERTISE REQUIRED:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

Call Order: 001 Proposal: E5V10

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0431- 1-238	PIPE LINING- OPTIONAL MATERIALS, 0-24" PROJECT 441928-1-72-02	LF	1,400.000
	0431- 1-239	PIPE LINING- OPTIONAL MATERIALS, 25-36" PROJECT 441928-1-72-02	LF	1,633.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000