



Florida Department of Transportation

RON DESANTIS
GOVERNOR

719 South Woodland Boulevard
DeLand, FL 32720

KEVIN J. THIBAUT, P.E.
SECRETARY

Questions and Answers #2

Contract No.: E5L30

Description: Leesburg Roof System Replacement

Date: February 17, 2021

1. In lieu of installing a gypsum cover board, can we fasten ½" plywood into the steel deck to serve as new substrate for roofing materials?

Response: Provide Fiberglass Mat Faced Gypsum Roof Board as indicated in the contract documents. The existing building is non-combustible construction, and we recommend the roof also be of noncombustible construction.

2. The spec calls for replacement of wet insulation. What is the current thickness?

Response: "R" Value 19 in. accordance with PIMA Technical Bulletin 101.; 3 inches thickness.