## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 05191001 Call Order: 011 Proposal: E5Z84 District:05

Counties: VOLUSIA

Road Name: - BIKE PATH/TRAIL

Limits: Midpoint

Project(s): 43643425201(\*) Federal Aid No: N/A

Total Roadway Length:0.000 MilesContract Days:90Total Bridge Length:0.000 MilesLetting Date:10/01/19Total Proposal Length:0.000 MilesContract Execution Days:10

Special Start Date: N/A

Aquis/Flexible Start Time: 30

Proposal Budget Estimate: \$342,891.00

Please read the full advertisement

## Description:

The Improvements under this Contract consist of constructing a ten to twelve foot wide asphalt shared use path with signing and markings, and milling and resurfacing at existing driveways, from Lake Monroe Park Entrance on US 17 to Old Deland Rd., approximately 0.37 miles in Volusia County.

The summary of pay items for this project is listed in the Plans.

BUSINESS DEVELOPMENT INITIATIVE -- Bidders must be a "Small Business" as defined by FDOT. Small business size standards can be found at https://www.fdot.gov/equalopportunity/bdi.shtm

For more information about bidding on BDI projects, please see the training guide located at http://www.cmdp-bgp.com/bdi-projects.html

Prequalification per Rule 14-22 is not required.

Bidders must complete and submit the Small Business Affidavit (Form No. 275-000-01) for approval prior to receipt of bid documents. The form may be accessed at: https://www.fdot.gov/equalopportunity/bdi.shtm

It is only necessary to submit the Small Business Affidavit (SBA) form once per year.

Send a completed and notarized affidavit as an attachment to: fdot.bdi@dot.state.fl.us.

All Sublet work must be contracted to a small business or businesses as defined by the Department. The subcontractor must also submit a notarized Small Business Affidavit Form provided by the Department prior to the start of work.

Bidders must submit the BDI Reference Sheet (Form No. 275-000-02) with the bid unless bidder is prequalified in the project's major work type, per Rule 14-22, Florida Administrative Code.

Upload the completed BDI Reference Sheet (Form No. 275-000-02) as a zip file using the "File Attachment Upload" folder in AASHTOWare Project Bids. The BDI Reference Sheet may be found at: https://www.fdot.gov/equalopportunity/bdi.shtm

Proposal Guaranty of \$500 is required for bids over \$150,000 and my be in the form of a Cashier's Check, the BDI Bid or Proposal Bond (Form No. 375-020-16), or the standard Bid or Proposal Bond form (Form No. 375-020-09).

Call Order: 011 Proposal: E5Z84

ALT	Item	Description	Unit	Quantity		
Section 0001 Roadway						
	0101- 1-	MOBILIZATION (43643425201)	LS	1.000		
	0102- 1-	MAINTENANCE OF TRAFFIC (43643425201)	LS	1.000		
	0102- 60-	WORK ZONE SIGN	ED	1,530.000		
	0102-74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	180.000		

Call Order: 011 Proposal: E5Z84

		Oan Order: 011 110posai. E0204		
ALT	Item	Description	Unit	Quantity
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	14.000
	0104- 10- 3	SEDIMENT BARRIER	LF	2,406.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0107- 1-	LITTER REMOVAL	AC	4.260
	0107- 2-	MOWING	AC	2.580
	0110- 1- 1	CLEARING & GRUBBING (43643425201)	LS	1.000
	0110- 4-10	REMOVAL OF EXISTING CONCRETE	SY	34.000
	0120- 1-	REGULAR EXCAVATION	CY	574.000
	0120- 6-	EMBANKMENT	CY	188.000
	0160- 4-	TYPE B STABILIZATION	SY	3,950.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,488.000
	0327- 70- 1	MILLING EXIST ASPH PAVT, 1" AVG DEPTH	SY	350.000
	0334- 1-12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	258.800
	0334- 1-13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	28.900
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	1.000
	0425- 11-	MODIFY EXISTING DRAINAGE STRUCTURE	EA	1.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	33.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	16.000
	0430-982-625	MITERED END SECTION, OPTIONAL - ELLIPTICAL / ARCH, 18" CD	EA	2.000
	0520- 5-11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	17.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	18.000
	0527- 2-	DETECTABLE WARNINGS	SF	56.000
	0550- 10-410	FENCING, WOOD FENCE, 0.0-5.0'	LF	253.000
	0550- 10-420	FENCING, WOOD FENCE, 5.1-6.0'	LF	837.000
	0550- 60-111	FENCE GATE, TYPE A, SINGLE, 0-6.0' OPENING	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,161.000
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	111.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43643425201)	LS	1.000
Sectio	n 0002 Signing			
	0700- 1-11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	9.000
	0700- 1-50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	0.006
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12" (Includes 111' from Trafffc Control Plan Items)	LF	94.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	149.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.070
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	21.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43643425201)	LS	1.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	94.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	136.000