

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	05191001	Call Order: 013	Proposal: E5Z89	District:05
Counties:	ORANGE			
Road Name:	SR 426 (BRIDGE 750305) & SR 551 (BRIDGE 750482)			
Limits:	75090000			
Project(s):	44326815201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.078 Miles	Contract Days:	110	
Total Bridge Length:	0.010 Miles	Letting Date:	10/01/19	
Total Proposal Length:	0.088 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	

Proposal Budget Estimate: \$409,692.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of culvert de-silting, concrete restoration, and shotcrete repairs. Located in Orange County, Florida (750900, 752000) Bridge No. 750482 carrying SR 551 (Goldenrod Road) over Drainage Canal from MP 5.665 to 5.671 & Bridge No. 750305 carrying SR 426 (Aloma Avenue) over Crane Strand Canal from MP 3.624 to 3.642.

PREQUALIFICATION REQUIRED

**Call Order: 013 Proposal: E5Z89**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	20.000
	0401- 70- 7	RESTORE SPALLED AREAS, SHOTCRETE	CF	1,293.000
	0411- 1-	EPOXY MATERIAL FOR CRACK INJECTION- STRUCTURES REHAB	GA	12.000
	0411- 2-	CRACKS INJECT & SEAL- STRUCTURES REHAB	LF	200.000
	0415- 1- 1	REINFORCING STEEL- ROADWAY	LB	112.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	314.000
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (44326815201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44326815201)	LS	1.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	225.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	62.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000