

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05201208	Call Order: 003	Proposal: E5V83	District:05
Counties:	BREVARD			
Road Name:	US 1 DRAINAGE OUTFALL REPAIR			
Limits:	Midpoint			
Project(s):	42927617222(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	80	
Total Bridge Length:	0.000 Miles	Letting Date:	12/08/20	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID No.: E5V83
Financial Project No.: 429276-1-72-22
Fiscal Year: 2021
County: Brevard
Calendar Days: 80
Lead Time: 14 Days

This is a Maintenance Pay Item Project.

The work under this Contract consists of repair of a drainage outfall off of US 1, including, culvert and structures installation, excavation, and site restoration.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of drainage repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E5V83

ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	676.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	66.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	1.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	63.000
	0120- 6-	EMBANKMENT	CY	1,150.000
	0425- 1-503	INLETS, DT BOT, TYPE A, J BOT, <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0430-175-260	PIPE CULVERT, OPT MATERIAL, OTHER SHAPE - ELIP/ARCH, 60"S/CD	LF	172.000
	0430-560-102	STRAIGHT CONCRETE ENDWALLS, 60", SINGLE, 0 DEGREES, ELLIPTICAL	EA	1.000
	0530- 4- 6	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 6"	SY	307.000
	0530- 74-	BEDDING STONE	TN	80.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	971.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID	LS	1.000