

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05200204	Call Order: 003	Proposal: E52A0	District:05
Counties:	BREVARD			
Road Name:	SR 518 EAU GALLE BLVD			
Limits:	70120004			
Project(s):	44417615201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.262 Miles	Contract Days:	90	
Total Bridge Length:	0.000 Miles	Letting Date:	02/04/20	
Total Proposal Length:	0.262 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	60	

Proposal Budget Estimate: \$821,776.00

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing and widening SR 518 Eau Galle Blvd. from W of Mosswood Dr. To E of Steward Ave in Brevard County. Work includes widening SR518 to add a left turn lane, new sidewalk, new curbing, roadway striping, highway signing and drainage work.

The summary of pay items for this project is listed in the Plans.

PREQUALIFICATION REQUIRED

Call Order: 003 Proposal: E52A0

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44417615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44417615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,600.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	180.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	540.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,339.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	1.840
	0107- 2-	MOWING	AC	1.400
	0110- 1- 1	CLEARING & GRUBBING (44417615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	859.000
	0120- 1-	REGULAR EXCAVATION	CY	31.000
	0120- 6-	EMBANKMENT	CY	174.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	1,367.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	1,671.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	6,542.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	363.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	790.200
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	7.000

Call Order: 003 Proposal: E52A0

ALT	Item	Description	Unit	Quantity
	0425- 1-361	INLETS, CURB, TYPE P-6, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	2.000
	0425- 2- 61	MANHOLES, P-8, <10'	EA	1.000
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	2.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	225.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	704.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	4.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	200.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	1,240.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	58.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	799.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	233.000
	0527- 2-	DETECTABLE WARNINGS	SF	43.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,233.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.260
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.260
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44417615201)	LS	1.000
Section 0002 Signing				
	0102- 75- 2	TEMPORARY SEPARATOR, F&I REMAIN	LF	194.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	2.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	2.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	5.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	2.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44417615201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	68.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	12.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.072
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	9.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	142.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	12.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.585
	0711- 16-131	THERMOPLASTIC, OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.551
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.684