Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05200602 Call Order: 001 Proposal: E54A5 District:05

Counties: BREVARD

Road Name: SR 518 EAU GALLE BLVD

Limits: 70120004

Project(s): 44417615201(*) Federal Aid No: N/A

Total Roadway Length:	0.262 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	06/02/20
Total Proposal Length:	0.262 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: $838,432.00

Please read the full advertisement

Description:

The improvements under this Contract consist of milling and resurfacing and widening SR 518 Eau Galle Blvd. from W of Mosswood Dr. To E of Steward Ave in Brevard County. Work includes widening SR518 to add a left turn lane, new sidewalk, new curbing, roadway striping, highway signing and drainage work.

The summary of pay items for this project is listed in the Plans.

PREQUALIFICATION REQUIRED

Call Order: 001 Proposal: E54A5

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44417615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44417615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	6,600.000
	0102- 74- 2	CHANNELIZING DEVICE, TYPE III, 6'	ED	180.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	540.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	180.000
	0104- 10- 3	SEDIMENT BARRIER	LF	1,339.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	9.000
	0107- 1-	LITTER REMOVAL	AC	5.510
	0107- 2-	MOWING	AC	4.190
	0110- 1- 1	CLEARING & GRUBBING (44417615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	859.000
	0120- 1-	REGULAR EXCAVATION	CY	174.000
	0120- 6-	EMBANKMENT	CY	35.000
	0285-712-	OPTIONAL BASE, BASE GROUP 12	SY	1,367.000
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	1,671.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	6,542.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	363.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	790.200
	0425- 1-351	INLETS, CURB, TYPE P-5, <10'	EA	7.000