Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05200303 Call Order: 002 Proposal: E50A9 District:05

Counties: BREVARD

Road Name: SR 404 FROM CR 509 TO SR A1A - BRIDGE-REPAIR/REHABILITATION

Limits: 70004000

Project(s): 44326415201(*) Federal Aid No: N/A

Total Roadway Length:	0.648 Miles	Contract Days:	180
Total Bridge Length:	1.242 Miles	Letting Date:	03/03/20
Total Proposal Length:	1.890 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: $1,832,867.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of replacement of fender timber components with composite lumber, replacement of associated hardware and wire ropes, and salvaging and re-installation of navigation lights with associated temporary lighting and electrical work at SR 404 over Indian River (Bridge Nos. 700077 and 700143) and SR 404 over Banana River (Bridge Nos. 700081 and 700147) in Brevard County.

PREQUALIFICATION REQUIRED

Call Order: 002 Proposal: E50A9

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 82-	REMOVE & DISPOSE OF STRUCTURAL TIMBER	MB	47.900
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	10.000
	0455- 76-	WRAP PILE CLUSTERS	EA	196.000
	0471- 1- 1	FENDER SYSTEM,PLASTIC MARINE LUMBER,REINFORCED	MB	43.500
	0471- 1- 2	FENDER SYSTEM,PLASTIC MARINE LUMBER, NON-REINFORCED	MB	11.300
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (44326415201)	LS	1.000
	0510- 1-	NAVIGATION LIGHTS- FIXED BRIDGE, SYSTEM (44326415201)	LS	1.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44326415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44326415201)	LS	1.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	2,400.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44326415201)	LS	1.000