

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 05201103      Call Order: 002      Proposal: E52A8      District:05

Counties: FLAGLER

Road Name: FLAGLER WEIGH STATION - SIGNING AND PAVEMENT MARKINGS

Limits: 73001000

Project(s): 44530915215(\*)

Federal Aid No: N/A

Total Roadway Length:	2.264 Miles	Contract Days:	70
Total Bridge Length:	0.000 Miles	Letting Date:	11/03/20
Total Proposal Length:	2.264 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	60

Proposal Budget Estimate: \$514,497.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of Highway Signing, Pavement Marking, and other incidental construction at the NB & SB Weigh Station on SR 9 (I-95) in Flagler County.

The summary of pay items for this project is listed in the Plans.

**PREQUALIFICATION REQUIRED**

**Call Order: 002 Proposal: E52A8**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44530915215)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44530915215)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	700.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,150.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	70.000
	0102-115-	TYPE III BARRICADE	ED	140.000
	0107- 1-	LITTER REMOVAL	AC	69.740
	0107- 2-	MOWING	AC	63.260
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44530915215)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	97.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	38.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	120.000
	0700- 2- 12	MULTI- POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	4.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	9.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	4.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	4.000
	0700- 11-262	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- SOLAR POWERED, SPEED FEEDBACK W/FLASHING BEACON, 12-20 SF	EA	2.000

**Call Order: 002 Proposal: E52A8**

ALT	Item	Description	Unit	Quantity
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	2.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	1,314.000
	0709- 12-130	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 6", FOR MCSAW PROJECTS	GM	5.824
	0709- 12-131	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID 8" FOR INTERCH & URBAN ISLAND, FOR MCSAW PROJECTS	GM	0.744
	0709- 12-132	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK, FOR MCSAW PROJECTS	LF	132.000
	0709- 12-133	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, FOR MCSAW PROJECTS	LF	1,633.000
	0709- 12-134	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SOLID, 24" FOR CROSSWALK, FOR MCSAW PROJECTS	LF	300.000
	0709- 12-135	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, WHITE, SKIP, 6", FOR MCSAW PROJECTS	GM	0.157
	0709- 12-136	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID, 6", FOR MCSAW PROJECTS	GM	3.285
	0709- 12-137	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID 8" FOR INTERCH & URBAN ISLAND, FOR MCSAW PROJECTS	GM	0.256
	0709- 12-138	TRAFFIC STRIPE-TWO REACTIVE COMPONENTS, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, FOR MCSAW PROJECTS	LF	639.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	77.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	91.000
	0711- 11-421	THERMOPLASTIC, STANDARD, BLUE, SOLID,6"	LF	527.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	6.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	12.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	31,838.000