

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 05201103      Call Order: 003      Proposal: E5V75      District:05

Counties: LAKE

Road Name: Highway Signing & Thermoplastic Pavement Markings

Limits:  
Midpoint

Project(s): 42795717227(\*)

Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	60
Total Bridge Length:	0.000 Miles	Letting Date:	11/03/20
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$250,000.00

Please read the full advertisement

Description:

FDOT District 5  
Proposal ID No.: E5V75  
Financial Project No.: 427957-1-72-27  
Fiscal Year: 2021  
County: Lake  
Contract Calendar Days: 60  
Lead Time: 14 Days

This is a Pay Item Maintenance Contract.

Intent:

The work includes the installation of highway signage and thermoplastic pavement markings on SR 33 in Lake County.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of pavement markings, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Pavement Markings" will suffice to meet the above requirements.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: E5V75**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 TRAFFIC CONTROL DEVICES CONTROL (MH)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (42795717227)	LS	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	49.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	35.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	10.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	48.000
	0700- 2- 13	MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	4.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	32.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	65.000
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	4.119
	0701- 18-221	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SKIP,6"	GM	1.999
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	24.000
	0706- 1- 1	RAISED PAVEMENT MARKER, TYPE B WITHOUT FINAL SURFACE MARKINGS	EA	845.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	44.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.016
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	30.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	30.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.018
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.032
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.135
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	4,685.000