

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 05201006      Call Order: 004      Proposal: E5V49-R0      District:05  
Counties: ORANGE, SEMINOLE  
Road Name: DRAINAGE REPAIR  
Limits: Midpoint  
Project(s): 44192817204(\*)      Federal Aid No: N/A  
Total Roadway Length: 0.000 Miles      Contract Days: 730  
Total Bridge Length: 0.000 Miles      Letting Date: 10/06/20  
Total Proposal Length: 0.000 Miles      Contract Execution Days: 10  
Special Start Date: N/A  
Aquis/Flexible Start Time:

Proposal Budget Estimate: \$1,101,000.00

Please read the full advertisement

**Description:**

FDOT District 5  
Proposal ID No.: E5V49  
Financial Project No.: 441928-1-72-04  
Fiscal Year: 2021  
Counties: Seminole & Orange  
Calendar Days: 730

This is a Maintenance Work Document driven Contract with a budgetary ceiling of \$1,101,000.

**Intent:**

The work includes desilting, video, cleaning, joint sealing, pipe lining, and manhole cover adjustment & replacement on the Department's stormwater system in various locations.

**Experience:**

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of drainage repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Note:**

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E5V49-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)</b>				
	0425- 5-	MANHOLE, ADJUST	EA	50.000
	0425- 7-	MANHOLE COVER- REPLACE	EA	50.000
	0425- 16- 11	DRAINAGE MANHOLE- REPLACE TOP AND RIM	EA	30.000
	0430-821- 23	CLEANING & SEALING EXISTING PIPE JOINT, 15" STORM SEWER	EA	100.000
	0430-821- 25	CLEANING & SEALING EXISTING PIPE JOINT, 18" STORM SEWER	EA	100.000
	0430-821- 29	CLEANING & SEALING EXISTING PIPE JOINT, 24" STORM SEWER	EA	200.000
	0430-821- 33	CLEANING & SEALING EXISTING PIPE JOINT, 30" STORM SEWER	EA	200.000
	0430-821- 38	CLEANING & SEALING EXISTING PIPE JOINT, 36" STORM SEWER	EA	200.000
	0430-821- 40	CLEANING & SEALING EXISTING PIPE JOINT, 42", STORM SEWER	EA	200.000
	0430-821- 41	CLEANING & SEALING EXISTING PIPE JOINT, 48", STORM SEWER	EA	100.000
	0430-821- 42	CLEANING & SEALING EXISTING PIPE JOINT, 54", STORM SEWER	EA	50.000
	0430-821- 43	CLEANING & SEALING EXISTING PIPE JOINT, 60", STORM SEWER	EA	50.000
	0430-821- 61	CLEANING & SEALING EXISTING PIPE JOINT, >60", STORM SEWER	EA	50.000
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	400.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	50.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	1,200.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	1,000.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	1,000.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	500.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	500.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	500.000
	E431- 1- 22	PIPE LINER, CURED IN PLACE, 25-36"	LF	500.000
	E431- 1- 23	PIPE LINER, CURED IN PLACE, 37-48"	LF	200.000
	E431- 1- 24	PIPE LINER, CURED IN PLACE, 49-60"	LF	100.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	100.000
	E431- 1- 31	PIPE LINER, SLIP LINER, 0-24"	LF	500.000
	E431- 1- 32	PIPE LINER, SLIP LINER, 25-36"	LF	500.000
	E431- 1- 33	PIPE LINER, SLIP LINER, 37-48"	LF	100.000
	E431- 1- 34	PIPE LINER, SLIP LINER, 49-60"	LF	100.000
	E431- 1- 35	PIPE LINER, SLIP LINER, 61" AND GREATER	LF	100.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	8,000.000