

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05201006 Call Order: 006 Proposal: E5V62 District: 05
 Counties: ORANGE
 Road Name: Pavement Markings and Raised Pavement Markers
 Limits: Midpoint
 Project(s): 42916017206(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: 350
 Total Bridge Length: 0.000 Miles Letting Date: 10/06/20
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$1,710,000.00

Please read the full advertisement

Description:

FDOT District 5
 Proposal ID No. E5V62
 Financial Project No.: 429160-1-72-06
 Fiscal Year: 2021

County: Orange
 Contract Calendar Days: 350
 Lead Time: 14 Calendar Days

This is a Maintenance Pay Item Project.

INTENT AND SCOPE:

Work under this Contract consists of removal of existing thermoplastic and preformed tape pavement markings, installation of thermoplastic and preformed tape pavement markings, installation of painted pavement markings, refurbishment of existing thermoplastic pavement markings and removal and installation of raised pavement markers.

EXPERIENCE:

For this Contract, the Contractor is required to have at least three (3) years of experience in the performance of Pavement Marking, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Pavement Markings" will suffice to meet the above requirements.

Call Order: 006 Proposal: E5V62

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	8,210.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	498.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	6,923.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.732
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	23.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	365.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	30.000

Call Order: 006 Proposal: E5V62

ALT	Item	Description	Unit	Quantity
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	2,024.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.048
	0711- 12-101	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6"	GM	97.030
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8" FOR MAINTENANCE USE	LF	54,375.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT- MAINTENANCE USE ONLY	LF	88,770.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	12,986.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK, MAINTENANCE USE ONLY	LF	26,862.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	98.271
	0711- 12-141	THERMOPLASTIC, REFURBISHMENT, WHITE, 2-4 DOTTED GUIDELINE / 6-10 GAP EXTENSION, 6", MAINTENANCE USE ONLY	GM	21.189
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	247.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	1,802.000
	0711- 12-201	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6"	GM	65.545
	0711- 12-222	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 8" MAINTENANCE USE ONLY	LF	7,296.000
	0711- 12-224	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	7,128.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	2.999
	0711- 12-241	THERMOPLASTIC, REFURBISHMENT, YELLOW 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" MAINT USE ONLY	GM	3.491
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	5,475.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	955.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	513.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	513.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	10.465
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.584
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",1C-30 SKIP OR 3-9 LANE DROP	GM	9.901
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	5.816
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.675
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	18,461.000
E706-	1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	18,760.000