Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 05200901 Call Order: 011 Proposal: E5V77 District:05

Counties: BREVARD

Road Name: SR 528 Drainage Repair

Limits: Midpoint

Project(s): 42927617221(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 60

Total Bridge Length: 0.000 Miles Letting Date: 09/01/20

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A
Aguis/Flexible Start Time: 14

Proposal Budget Estimate: \$300,000.00

Please read the full advertisement

Description: FDOT District 5

Proposal ID No.: E5V77

Financial Project No.: 429276-1-72-21

Fiscal Year: 2021 County: Brevard Calendar Days: 60 Lead Time: 14 Days

This is a Maintenance Pay Item Contract.

Intent:

The work under this Contract consists of the installation of a drainage culvert by jack & bore, construction of end walls, and plugging the existing culvert, located on SR 528 east of the US 1 interchange in Brevard County.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of drainage repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

Call Order: 011 Proposal: E5V77

		• • • • • • • • • • • • • • • • • • •		
ALT	Item	Description	Unit	Quantity
Sectio	n 0001 REPAIR/R	EPLACE STRM-SIDE-CROSS DRAIN(LF)		
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	353.000
	0110- 1- 1	CLEARING & GRUBBING (42927617221)	LS	1.000
	0120- 1-	REGULAR EXCAVATION	CY	1,420.000
	0120- 6-	EMBANKMENT	CY	73.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	19.000
	0430-185-136	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, JACK & BORE, 36", STORM AND CROSS DRAIN	LF	216.000
	0430-536-100	STRAIGHT CONCRETE ENDWALLS, 36", SINGLE, 0 DEGREES, ROUND	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	32.500
	0524- 1-19	CONCRETE DITCH PAVT, 3", REINFORCED	SY	178.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	1,776.000