

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	05210406	Call Order: 003	Proposal: E5X14	District:05
Counties:	LAKE			
Road Name:	Asphalt Roadway Depression Repair			
Limits:	Midpoint			
Project(s):	42915717219(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	45	
Total Bridge Length:	0.000 Miles	Letting Date:	04/06/21	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$165,000.00

Please read the full advertisement

**Description:**

FDOT District 5  
Proposal ID No. : E5X14  
Financial Project No.: 429157-1-72-19  
Fiscal Year: 2021  
County: Lake  
Calendar Days: 45  
Lead Time: 14 Days

This is a Maintenance Pay Item Contract

Intent: The work under this contract includes sinkhole repair and associated work on SR 44 in Lake County.

**Experience:**

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of asphalt paving projects, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course" will suffice to meet the above requirements.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 003 Proposal: E5X14**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MANUAL) (TN)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	75.000
	0120- 1-	REGULAR EXCAVATION	CY	22.670
	0120- 6-	EMBANKMENT	CY	7.600
	0160- 4-	TYPE B STABILIZATION	SY	72.670
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	22.670
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	181.330
	0334- 1- 54	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC D, PG76-22	TN	22.670
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	14.960
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	70.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	58.330
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.030
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.030
	0906-173- 33	SINGLE COMPONENT POLYURETHANE INJECTION, PROJECT 429157 -1-72-19	GA	6,859.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	4.000