



Florida Department of Transportation

RON DESANTIS
GOVERNOR

719 South Woodland Boulevard
DeLand, FL 32720

KEVIN J. THIBAUT, P.E.
SECRETARY

March 17, 2021

ADDENDUM NO. 3

To: PROSPECTIVE BIDDERS AND PLAN HOLDERS

FINANCIAL PROJECT NUMBER: 429157-1-72-19

CONTRACT NUMBER: E5X14

COUNTY: Lake

DESCRIPTION: Asphalt Roadway Depression Repair

SPECIFICATION PACKAGE REVISION

Page 53 of the Specification Package has been revised. Please substitute this sheet for the like numbered sheet in the Specification Package you now have.

Please go to the online ordering website at

<https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download the document titled E5X14Addendum3

AMENDMENT NOTIFICATION

If you are a BID DOCUMENT HOLDER for the subject project, please go to the Online Ordering Website at <https://fdotwp1.dot.state.fl.us/contractproposalprocessingonlineordering/> to download Amendment File E5X14.003x for this Bid Document from your Order History.

If you are a BID DOCUMENT HOLDER, please acknowledge receipt of this Addendum in AASHTOWare Project Bids by opening the Acceptance of Bidding Acknowledgements folder and confirming your acknowledgement of Amendment and Addenda files. Failure to load all amendment files will cause the bid to be rejected.

Sincerely,

DocuSigned by:

Jeanne Peeney

District Contracts Administrator
District 5

TABLE 1

Summary of Polyurethane Grout Quantity Estimates

Depressed Area on S.R. 44 at South Palmetto Street

Leesburg, Lake County, Florida

Task Work Order No. 7.16A

Pay Item	Grout Injection Points	Total Grout Program
Polyurethane Injection SINGLE COMPONENT	66	722 gallons

Notes:

1. Quantities should be considered rough approximations only. Actual quantities may be much higher or lower and will be determined during the remediation program.
2. Grout quantity based on an assumed 1 gallon per linear foot plus an additional contingency of 2 gallons per grout injection point.
3. Injection point spacings and grout quantities should be considered preliminary and may be adjusted (or locations added/deleted) based on the Contractor's specific proposed products and work methodology.