

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05211207 Call Order: 005 Proposal: E5V57-R0 District:05
 Counties: BREVARD, DIST/ST-WIDE, FLAGLER, LAKE, MARION, ORANGE, OSCEOLA, SEMINOLE, SUMTER, VOLUSIA
 Road Name: Signal Repair
 Limits: Midpoint
 Project(s): 42795717224(*) Federal Aid No: N/A
 Total Roadway Length: 0.000 Miles Contract Days: 730
 Total Bridge Length: 0.000 Miles Letting Date: 12/07/21
 Total Proposal Length: 0.000 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time:
 Proposal Budget Estimate: \$500,000.00

Please read the full advertisement

Description:

FDOT District 5
 Proposal ID No.: E5V57
 Financial Project No.: 427957-1-72-24
 Fiscal Year: 2022
 Counties: Districtwide (Volusia, Flagler, Brevard, Orange, Osceola, Lake, Marion, Sumter, Seminole)
 Contract Calendar Days: 730

This is a Maintenance Work Document driven Contract with a budgetary ceiling of \$500,000.00. This Contract has an option of one renewal of twelve months.

Intent: The work under this Contract includes traffic operational and safety improvements. The improvements include, but are not limited to, installation, repair, and/or modification of traffic signalized intersections, signing and pavement markings, minor concrete improvements, and pedestrian feature installations (I.e.: ADA curb ramps and crosswalks, standard and accessible pedestrian button installations, midblock crossings, RRFBs, PHBs, etc.).

Experience: For this Contract, the Contractor is required to have at least three (3) years of experience in the performance of Traffic Signal Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Traffic Signal" will suffice to meet the above requirements.

Note: The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
Section 0001 TRAFFIC CONTROL (MH)				
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	150.000
	0102- 60-	WORK ZONE SIGN	ED	1,500.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	3,000.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	1,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	50.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	50.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0102-115-	TYPE III BARRICADE	ED	20.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	10.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	10.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	10.000
	0527- 2-	DETECTABLE WARNINGS	SF	400.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	200.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,000.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	1,000.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	1,000.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	5.000
	0632- 7- 2	SIGNAL CABLE- REPAIR/REPLACE/OTHER, FURNISH & INSTALL	LF	1,000.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	5.000
	0633- 1-111	FIBER OPTIC CABLE, F&I, OVERHEAD,2-12 FIBERS	LF	1,000.000
	0633- 1-112	FIBER OPTIC CABLE, F&I, OVERHEAD,13-48 FIBERS	LF	1,000.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,000.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	1,000.000
	0633- 1-610	FIBER OPTIC CABLE, REMOVE, OVERHEAD	LF	1,000.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	1,000.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	10.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	10.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	4.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	4.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	4.000
	0633- 3- 15	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED PATCH PANEL	EA	4.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	4.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	4.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	4.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	1,000.000
	0633- 8- 3	MULTI-CONDUCTOR COMMUNICATION CABLE, INSTALL	LF	500.000
	0633- 8- 4	MULTI-CONDUCTOR COMMUNICATION CABLE, RELOCATE	LF	1,000.000
	0634- 4-152	SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL	PI	10.000
	0634- 4-153	SPAN WIRE ASSEMBLY, F&I, TWO POINT, BOX OR DROP BOX	PI	10.000
	0634- 4-600	SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN	PI	10.000
	0634- 5- 1	FIBERGLASS INSULATOR, FURNISH & INSTALL	LF	1,000.000
	0634- 6- 1	MESSENGER WIRE, FURNISH & INSTALL- REPLACE EXISTING	LF	1,000.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	10.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	10.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	10.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	10.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	10.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,000.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	4.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	4.000
	0641- 1- 1	GUYING EXISTING CONCRETE STRAIN POLE	EA	5.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 16	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VI	EA	4.000
	0641- 2- 17	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VII	EA	4.000
	0641- 2- 18	PRESTRESSED CONCRETE POLE, F&I, TYPE P-VIII	EA	4.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0641- 2- 80	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- POLE 30' AND GREATER	EA	4.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	20.000
	0646- 1- 12	ALUMINUM SIGNALS POLE, FURNISH & INSTALL PEDESTRIAN DETECTOR POST	EA	40.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	20.000
	0649- 26- 1	STEEL MAST ARM ASSEMBLY, REMOVE, POLE ONLY- ENTIRE FOUNDATION REMAINS	EA	1.000
	0649- 26- 3	STEEL MAST ARM ASSEMBLY, REMOVE, SHALLOW FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0649- 26- 7	STEEL MAST ARM ASSEMBLY, REMOVE, REMOVE ARM AND ATTACHMENTS; POLE REMAINS	EA	1.000
	0650- 1- 11	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 1 WAY	AS	15.000
	0650- 1- 12	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 1 SECTION, 2-4 WAY	AS	15.000
	0650- 1- 14	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY	AS	15.000
	0650- 1- 15	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 2-4 WAYS	AS	15.000
	0650- 1- 16	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 1 WAY	AS	15.000
	0650- 1- 17	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 4 SECTION, 2-4 WAYS	AS	15.000
	0650- 1- 19	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY	AS	10.000
	0650- 1- 24	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 3 SECTION, 1 WAY	AS	15.000
	0650- 1- 25	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE WITH ALUMINUM TOP SECTION, 3 SECTION, 2-4 WAYS	AS	15.000
	0650- 1- 26	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 4 SECTION, 1 WAY	AS	15.000
	0650- 1- 29	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W ALUMIN, 5 SECTION CLUSTER, 1 WAY	AS	15.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	15.000
	0650- 1- 35	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 2-4 WAYS	AS	15.000
	0650- 1- 36	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 4 SECTION, 1 WAY	AS	15.000
	0650- 1- 39	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 5 SECTION CLUSTER, 1 WAY	AS	15.000
	0650- 1- 50	VEHICULAR TRAFFIC SIGNAL, INSTALL	AS	15.000
	0650- 1- 60	VEHICULAR TRAFFIC SIGNAL, REMOVE- POLES TO REMAIN	AS	15.000
	0650- 1- 70	VEHICULAR TRAFFIC SIGNAL, RELOCATE- INCLUDES REMOVAL AND REINSTALLATION	AS	15.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	15.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	15.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	15.000
	0653- 1- 12	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS	AS	15.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	15.000
	0654- 2- 11	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- AC, COMPLETE SIGN ASSEMBLY- SINGLE DIRECTION	AS	10.000
	0654- 2- 17	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH/INSTALL- AC, SIGN ASSY- SINGLE DIR ACCESSIBLE DETECTOR	AS	10.000
	0654- 2- 18	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- AC, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR	AS	10.000
	0654- 2- 21	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, FURNISH & INSTALL- SOLAR, COMPLETE SIGN ASSY- SINGLE DIRECTION	AS	10.000
	0654- 2- 27	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- SINGLE DIR ACCESSIBLE DETECTOR	AS	10.000
	0654- 2- 28	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- SOLAR, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR	AS	10.000
	0654- 2- 30	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, INSTALL COMPLETE SIGN ASSEMBLY	AS	10.000
	0654- 2- 40	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, RELOCATE COMPLETE SIGN ASSEMBLY	AS	10.000
	0654- 2- 50	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, ADJUST/MODIFY	AS	10.000
	0654- 2- 60	MIDBLOCK CROSSWALK: RECTANGULAR RAPID FLASHING BEACON, REMOVE COMPLETE SIGN ASSEMBLY	AS	10.000
	0654- 3- 10	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, FURNISH & INSTALL COMPLETE ASSEMBLY	AS	10.000
	0654- 3- 60	MIDBLOCK CROSSWALK: PEDESTRIAN HYBRID BEACON ASSEMBLY, REMOVE	AS	10.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	20.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	20.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	20.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	20.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	5.000
	0660- 3- 31	VEHICLE DETECTION SYSTEM- MICROWAVE, INSTALL- FDOT FURNISHED CABINET EQUIPMENT	EA	5.000
	0660- 3- 32	VEHICLE DETECTION SYSTEM- MICROWAVE, INSTALL- FDOT FURNISHED, ABOVE GROUND EQUIPMENT	EA	5.000
	0660- 4- 11	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT	EA	5.000
	0660- 4- 12	VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT	EA	5.000
	0660- 4- 42	VEHICLE DETECTION SYSTEM- VIDEO, RELOCATE ABOVE GROUND EQUIPMENT	EA	5.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	5.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	5.000
	0663- 1-121	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, REPLACE CABINET ELECTRONICS	EA	5.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	5.000
	0663- 1-400	SIGNAL PRIORITY & PREEMPTION SYSTEM, RELOCATE	EA	5.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	30.000
	0665- 1- 12	PEDESTRIAN DETECTOR, FURNISH & INSTALL, ACCESSIBLE	EA	30.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	15.000
	0670- 4- 1	INTERSECTION CONTROL BEACON CONTROLLER ASSEMBLY, FURNISH & INSTALL	AS	5.000
	0670- 5-110	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA	AS	2.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	2.000
	0670- 5-112	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 2 PREEMPTION	AS	2.000
	0670- 5-140	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL MODEL 207	AS	5.000
	0670- 5-141	TRAFFIC CONTROLLER ASSEMBLY, FURNISH & INSTALL, MODEL 2070, 1 PREEMPTION	AS	5.000
	0670- 5-300	TRAFFIC CONTROLLER ASSEMBLY, INSTALL	AS	2.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	2.000
	0670- 5-500	TRAFFIC CONTROLLER ASSEMBLY, RELOCATE CONTROLLER WITH CABINET	AS	2.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	10.000
	0670- 5-700	TRAFFIC CONTROLLER ASSEMBLY, RESTORE- MINOR REPAIRS	AS	2.000
	0678- 1-107	CONTROLLER ACCESSORIES, REPLACE EXISTING- FURNISH AND INSTALL, TYPE 1 TIME SWITCH	EA	5.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	2.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	5.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0685- 1- 14	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, ONLINE/DOUBLE CONVERSION WITH CABINET	EA	5.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	2.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	2.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	2.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	2.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0695- 8- 11	TRAFFIC MONITORING SITE COMMUNICATIONS MODEM FURNISH & INSTALL	EA	2.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	50.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	10.000
	0700- 1- 21	SINGLE POST SIGN, F&I BARRIER MOUNT INDEX 11871/700-013 UP TO 12 SF	AS	5.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	10.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	50.000
	0700- 2- 50	MULTI- POST SIGN, GROUND MOUNT, RELOCATE	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-201	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	2.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	2.000
	0700- 3-502	SIGN PANEL, RELOCATE, 12-20 SF	EA	10.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	2.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	2.000
	0700- 5- 21	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF	EA	10.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	10.000
	0700- 5- 50	INTERNALLY ILLUMINATED SIGN, RELOCATE	EA	5.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	5.000
	0700- 6- 11	HIGHLIGHTED SIGN, F&I GROUND MOUNT- AC POWERED, UP TO 12 SF	AS	5.000
	0700- 6- 21	HIGHLIGHTED SIGN, F&I GROUND MOUNT- SOLAR POWERED, UP TO 12 SF	AS	5.000
	0700- 11-131	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, SPEED FEEDBACK SIGN, UP TO 12 SF	AS	1.000
	0700- 11-132	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, SPEED FEEDBACK SIGN, 12-20 SF	AS	1.000
	0700- 11-161	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, SPEED FEEDBACK W/FLASHING BEACON, UP TO 12 SF	AS	1.000
	0700- 11-162	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT- AC POWERED, SPEED FEEDBACK W/FLASHING BEACON, 12-20 SF	AS	1.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0700- 11-231	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT-SOLAR POWER, SPEED FEEDBACK, UP TO 12 SF	AS	1.000
	0700- 11-232	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT-SOLAR POWER, SPEED FEEDBACK, 12-20 SF	AS	1.000
	0700- 11-241	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT-SOLAR POWER, ELECT WARNING W/FLASHING BEACON, UP TO 12 SF	AS	1.000
	0700- 11-262	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL GROUND MOUNT-SOLAR POWERED, SPEED FEEDBACK W/FLASHING BEACON, 12-20 SF	EA	1.000
	0700- 11-391	ELECTRONIC DISPLAY SIGN, FURNISH & INSTALL OVERHEAD MOUNT- AC POWERED, BLANK OUT SIGN, UP TO 12 SF	AS	1.000
	0700- 12- 11	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, ONE BEACON	AS	5.000
	0700- 12- 12	SIGN BEACON, F&I GROUND MOUNT- AC POWERED, TWO BEACON	AS	5.000
	0700- 12- 21	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, ONE BEACON	AS	5.000
	0700- 12- 22	SIGN BEACON, F&I GROUND MOUNT- SOLAR POWERED, TWO BEACONS	AS	5.000
	0700- 12- 50	SIGN BEACON, RELOCATE BEACON- SIGN TO REMAIN	AS	2.000
	0700- 12- 60	SIGN BEACON, REMOVE BEACON- SIGN TO REMAIN	AS	2.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	3.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	100.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	200.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.500
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD,WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.500
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.500
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	0.500
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	100.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.250
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	800.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	800.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	600.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.500
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	8.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	8.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	40.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	450.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	1.000
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	800.000

Call Order: 005 Proposal: E5V57-R0

ALT	Item	Description	Unit	Quantity
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	600.000
	0711- 14-560	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST ON CONCRETE PAVEMENT, MESSAGE OR SYMBOL	EA	5.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	5.000
	0711- 14-660	THERMOPLASTIC, PREFORMED, MULTI COLOR ROUTE SHIELD	EA	5.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.500
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.500
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.500
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.500
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.500
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.500
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.250
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	100.000