

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05211207 Call Order: 006 Proposal: E5V82 District:05

Counties: VOLUSIA

Road Name: Drainage Repair- SR A1A Outfall @ Rockefeller Drive

Limits:

Project(s): 42798617225

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

180

Total Bridge Length:

0.000 Miles

Letting Date:

12/07/21

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

14

Proposal Budget Estimate:

\$1,530,772.00

Please read the full advertisement

Description:

FDOT District 5

Proposal ID No.: E5V82

Financial Project No: 427986-1-72-25

Fiscal Year: 2022

Counties: Volusia

Contract Calendar Days: 180

Lead Time: 14 days

This is a Maintenance Pay Item Project.

INTENT AND SCOPE:

The work under this Contract consists of stormwater pipe lining and repair of SR A1A outfall pipe at Rockefeller Drive in Ormond Beach, Volusia County.

EXPERIENCE:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: E5V82

ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0120- 6-	EMBANKMENT	CY	2.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	727.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	233.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	79.200
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	79.200
	0425- 5-	MANHOLE, ADJUST	EA	6.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	12.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	3.000
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	2,775.000