

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05211207 Call Order: 008 Proposal: E5X01 District:05

Counties: ORANGE

Road Name: Milling and Resurfacing

Limits:

Project(s): 44169617204

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

150

Total Bridge Length:

0.000 Miles

Letting Date:

12/07/21

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

14

Proposal Budget Estimate:

\$1,430,000.00

Please read the full advertisement

Description:

FDOT District 5

Proposal ID No.: E5X01

Financial Project No.: 441696-1-72-04

Fiscal Year: 2022

County: Orange

Contract Calendar Days: 180

Lead Time: 14 Calendar Days

This is a Maintenance Pay Item Project.

INTENT AND SCOPE:

Work under this Contract consists of asphalt milling and resurfacing, replacement of traffic loops, painted pavement markings, preformed thermoplastic markings and reflective pavement markers on various State Roads in Orange County.

EXPERTISE REQUIRED:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of asphalt paving projects, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course" will suffice to meet the above requirements.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 008 Proposal: E5X01

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	40.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	40.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	41,118.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,392.240
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	51.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	24.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	10.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	10.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.150
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.120
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	2,658.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	24.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	1,289.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	4.530
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	29.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.650
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.410
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	39.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	11.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	11.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	902.000