

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05211207 Call Order: 010 Proposal: E5X25 District:05

Counties: ORANGE

Road Name: Thermoplastic Pavement Markings and Raised Pavement Markers

Limits:

Project(s): 42916017207

Federal Aid No: N/A

Total Roadway Length:

0.000 Miles

Contract Days:

280

Total Bridge Length:

0.000 Miles

Letting Date:

12/07/21

Total Proposal Length:

0.000 Miles

Contract Execution Days:

10

Special Start Date:

N/A

Aquis/Flexible Start Time:

14

Proposal Budget Estimate:

\$410,000.00

Please read the full advertisement

Description:

FDOT District 5

Proposal ID No.: E5X25

Financial Project No.: 429160-1-72-07

Fiscal Year: 2022

County: Orange

Contract Calendar Days: 280

Lead Time: 14 Days

This is a Maintenance Pay Item Project.

INTENT AND SCOPE

Work under this Contract consists of installation of thermoplastic pavement markings, preformed thermoplastic pavement markings and raised pavement markers.

EXPERTISE REQUIRED:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Pavement Markings or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Pavement Markings" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 010 Proposal: E5X25

ALT	Item	Description	Unit	Quantity
Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	3,214.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	2,381.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,547.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	1.196
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	40.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	181.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	647.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.085
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	7.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	7.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	11.107
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	2.339
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	11.376
	0711- 16-133	THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.113
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.602
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	0.139
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.090
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	43,386.000