

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05210202	Call Order: 003	Proposal: E57A9	District:05
Counties:	ORANGE			
Road Name:	ORANGE COUNTY PEDESTRIAN LIGHTING BUNDLE H			
Limits:	75010000			
Project(s):	43988085201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.834 Miles	Contract Days:	30	
Total Bridge Length:	0.000 Miles	Letting Date:	02/02/21	
Total Proposal Length:	3.834 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90	

Proposal Budget Estimate: \$141,736.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of pedestrian intersection lighting improvements for US 17/92 (SR 600/500) from Land Street to Skyview Dr. in Orange County.

The summary of pay items for this project is listed in the Plans.

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 003 Proposal: E57A9

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43988085201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43988085201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43988085201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	480.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	690.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	240.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	30.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	37.000
	0102-115-	TYPE III BARRICADE	ED	60.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.030
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	59.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	59.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43988085201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	206.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	67.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,227.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	120.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	4.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	4.000
	0715-500- 11	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL	EA	5.000