

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05210202	Call Order: 003	Proposal: E57A9	District:05
Counties:	ORANGE			
Road Name:	ORANGE COUNTY PEDESTRIAN LIGHTING BUNDLE H			
Limits:	75010000			
Project(s):	43988085201(*)	Federal Aid No: N/A		
Total Roadway Length:	3.834 Miles	Contract Days:	30	
Total Bridge Length:	0.000 Miles	Letting Date:	02/02/21	
Total Proposal Length:	3.834 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90	

Proposal Budget Estimate: \$141,736.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of pedestrian intersection lighting improvements for US 17/92 (SR 600/500) from Land Street to Skyview Dr. in Orange County.

The summary of pay items for this project is listed in the Plans.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 003 Proposal: E57A9

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43988085201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43988085201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (43988085201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	480.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	690.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	240.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	30.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	37.000
	0102-115-	TYPE III BARRICADE	ED	60.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	4.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.030
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	59.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	59.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43988085201)	LS	1.000
Section 0002 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	206.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	67.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	1,227.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	120.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	5.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	4.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	4.000
	0715-500- 11	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL ALTERNATE SYSTEM, CONVENTIONAL	EA	5.000