

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 05210202      Call Order: 007      Proposal: E5V67-R0      District:05

Counties: LAKE, MARION, ORANGE

Road Name: PAVEMENT MARKINGS

Limits: Midpoint

Project(s): 42918217206(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	02/02/21
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	07/01/21
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$314,000.00

Please read the full advertisement

**Description:**

FDOT District 5  
 Proposal ID No.: E5V67  
 Financial Project No.: 429182-1-72-06  
 Fiscal Year: 2021  
 County: Marion, Lake, Orange  
 Contract Calendar Days: 365

This is a Work Document driven Maintenance Contract with a Budgetary Ceiling of \$314,000. Contract Time begins on July 1, 2021.

**Intent:**

The work under this Contract consists of removal and installation of pavement markings and RPMs on various State maintained roadways in Marion, Lake, and Orange Counties.

**Experience:**

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of pavement markings, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Pavement Markings" will suffice to meet the above requirements.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**Call Order: 007 Proposal: E5V67-R0**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 PAVEMENT STRIPING (LARGE MACHINE) (LM)</b>				
	0546- 71- 1	RAISED RUMBLE STRIP SET- PERMANENT	EA	3.000
	0546- 72- 2	GROUND-IN RUMBLE STRIPS, 8" CYLINDRICAL	GM	1.000
	0701- 18-101	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, WHITE, SOLID,6"	GM	2.000
	0701- 18-201	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SOLID,6"	GM	2.000
	0701- 18-221	PROFILED THERMOPLASTIC,STANDARD- ASPHALT SURFACES, YELLOW, SKIP,6"	GM	2.000

**Call Order: 007 Proposal: E5V67-R0**

ALT	Item	Description	Unit	Quantity
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	10.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	1.268
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	10.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.107
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	7,000.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	1,539.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,373.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	187.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	36.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	461.000
	0711- 12-121	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 6" FOR MAINTENANCE USE	LF	642.000
	0711- 12-122	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 8" FOR MAINTENANCE USE	LF	500.000
	0711- 12-123	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 12" FOR CROSS WALK OR ROUNDABOUT- MAINTENANCE USE ONLY	LF	1,200.000
	0711- 12-124	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	1,181.000
	0711- 12-125	THERMOPLASTIC, REFURBISHMENT, WHITE, SOLID, 24" FOR STOP LINE OR CROSSWALK, MAINTENANCE USE ONLY	LF	78.000
	0711- 12-131	THERMOPLASTIC, REFURBISHMENT, WHITE, SKIP, 6"	GM	0.053
	0711- 12-160	THERMOPLASTIC, REFURBISH, WHITE, MESSAGE	EA	3.000
	0711- 12-170	THERMOPLASTIC, REFURBISH, WHITE, ARROWS	EA	11.000
	0711- 12-221	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 6" MAINTENANCE USE ONLY	LF	400.000
	0711- 12-222	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 8" MAINTENANCE USE ONLY	LF	3,440.000
	0711- 12-224	THERMOPLASTIC, REFURBISHMENT, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON, MAINTENANCE USE ONLY	LF	500.000
	0711- 12-231	THERMOPLASTIC, REFURBISHMENT, YELLOW, SKIP, 6"	GM	2.000
	0711- 13-123	THERMOPLASTIC, HOT SPRAY, WHITE, SOLID, 12" MAINTENANCE USE ONLY	LF	250.000
	0711- 13-125	THERMOPLASTIC, HOT SPRAY, WHITE, SOLID, 24" MAINTENANCE USE ONLY	LF	250.000
	0711- 13-224	THERMOPLASTIC, HOT SPRAY, YELLOW, SOLID, 18" MAINTENANCE USE ONLY	LF	250.000
	0711- 16-202	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 8"	GM	1.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	90,000.000
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.250
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.250
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.250

**Call Order: 007 Proposal: E5V67-R0**

ALT	Item	Description	Unit	Quantity
	0713-103-231	PERMANENT TAPE, YELLOW, 10-30 SKIP/ 3-9 DOTTED, 6" FOR CONCRETE SURFACES	GM	0.250
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.250
	0713-103-333	PERMANENT TAPE, BLACK, 3'-9' DROP LANE, 12" ON CONCRETE SURFACES	GM	0.250
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	1,320.000
	E706- 1- 42	REFLECTIVE PAVEMENT MARKER(REMOVE AND REPLACE)(CLASS B)	EA	20,822.000
	E710- 11-121	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	LF	74,934.640
	E710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 6"	LF	47,562.240
	E710- 11-221	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	LF	56,561.280
	E710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	LF	11,365.760
	E710- 17-	REMOVAL OF NON-CONFLICTING PAINT/LOGLINE STRIPE PRIOR TO REFURBISH	SF	500.000
	E711- 3- 1	PAVEMENT MESSAGES (THERMOPLASTIC)	SF	44.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	25,000.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	7,744.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	15,000.000
	E711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, SKIP, 6"	LF	4,427.000