

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	05210105	Call Order: 002	Proposal: E53A9	District:05
Counties:	OSCEOLA			
Road Name:	SR 500/US 441/US 92/US 17 - RESURFACING			
Limits:	92010000			
Project(s):	44101715201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.734 Miles	Contract Days:	70	
Total Bridge Length:	0.000 Miles	Letting Date:	01/05/21	
Total Proposal Length:	0.734 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30	

Proposal Budget Estimate: \$662,426.00

Please read the full advertisement

Description:

SCOPE OF WORK – INTENT OF CONTRACT.

The improvements under this Contract consists of Milling and Resurfacing, Traffic Signals, and Signing/Pavement Markings on SR 500 from North of Cypress Street to Old Dixie Highway, approximately 0.367 miles in Osceola County.

The summary of pay items for this project is listed in the Plans.

PREQUALIFICATION REQUIRED

**Call Order: 002 Proposal: E53A9**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44101715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44101715201)	LS	1.000
	0102- 4-	PEDESTRIAN SPECIAL DETOUR (44101715201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	48.000
	0102- 60-	WORK ZONE SIGN	ED	1,746.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	108.000
	0102- 71- 23	TEMPORARY BARRIER, RELOCATE, LOW PROFILE CONCRETE	LF	108.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,848.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	2,856.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	119.000
	0102- 78-	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER	EA	291.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	140.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	70.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	70.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	11.000
	0107- 1-	LITTER REMOVAL	AC	1.180
	0110- 1- 1	CLEARING & GRUBBING (44101715201)	LS	1.000
	0210- 1- 9	REWORKING LIMEROCK BASE, 3"	SY	4,917.000
	0327- 70- 2	MILLING EXIST ASPH PAVT, 3 1/2" AVG DEPTH	SY	2,481.000

**Call Order: 002 Proposal: E53A9**

ALT	Item	Description	Unit	Quantity
	0327- 70- 4	MILLING EXIST ASPH PAVT, 3" AVG DEPTH	SY	10,563.000
	0327- 70- 6	MILLING EXIST ASPH PAVT, 1 1/2" AVG DEPTH	SY	637.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	1,144.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	1,120.000
	0515- 2-111	PEDESTRIAN / BICYCLE RAILING, NS, 42" TYPE 1	LF	147.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	8.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	1.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	1.468
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,540.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	384.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.468
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	4.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	30.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	1.468
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.468
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44101715201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	7.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	6.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44101715201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	565.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	37.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	113.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	16.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	186.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.754
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.634
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.614
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.403
<b>Section 0003 Signalization</b>				
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	4.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	4.000

**Call Order: 002 Proposal: E53A9**

---

ALT	Item	Description	Unit	Quantity
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000