

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting:	05210707	Call Order: 001	Proposal: E56A2	District:05
Counties:	VOLUSIA			
Road Name:	SR 15A			
Limits:	79160000			
Project(s):	44113415201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.993 Miles	Contract Days:	110	
Total Bridge Length:	0.000 Miles	Letting Date:	07/07/21	
Total Proposal Length:	0.993 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Acquisition	
Proposal Budget Estimate:	\$1,672,161.00			

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of milling and resurfacing, ADA and pedestrian safety enhancements, median opening reductions, and minor signalization improvements on State Road 15A from 500-ft south of Plymouth Ave. (MP 3.659) to 200-ft north of CR 92 (MP 4.652), approximately 0.993 miles in the City of DeLand, Volusia County, FL.

**PREQUALIFICATION REQUIRED**

**Call Order: 001 Proposal: E56A2**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (44113415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44113415201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44113415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	6,683.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	18,595.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	14,076.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	172.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	340.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	220.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	220.000
	0102-115-	TYPE III BARRICADE	ED	132.000
	0102-913- 11	REMOVABLE TAPE, BLACK, SOLID 6"	GM	0.358
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.148
	0102-913- 24	REMOVABLE TAPE, WHITE, 12" CROSSWALK	LF	101.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.220
	0104- 10- 3	SEDIMENT BARRIER	LF	272.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	37.000
	0107- 1-	LITTER REMOVAL	AC	26.040
	0107- 2-	MOWING	AC	12.220
	0110- 1- 1	CLEARING & GRUBBING (44113415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	664.000
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	34.300

**Call Order: 001 Proposal: E56A2**

ALT	Item	Description	Unit	Quantity
	0120- 71-	REGULAR EXCAVATION (3-R PROJECTS ONLY) (44113415201)	LS	1.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	19.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	18,084.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	2,603.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	21,253.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	1,494.600
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	3,532.800
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	6.000
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	1.000
	0425- 1-451	INLETS, CURB, TYPE J-5, <10'	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	4.000
	0430-175-115	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 15"S/CD	LF	4.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	8.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	115.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	968.000
	0520- 5- 12	TRAFFIC SEPARATOR CONCRETE-TYPE I, 6' WIDE	LF	50.000
	0520- 5- 16	TRAFFIC SEPARATOR CONCRETE- TYPE I, 8.5' WIDE	LF	114.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	97.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	358.000
	0527- 2-	DETECTABLE WARNINGS	SF	206.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	175.000
	0536- 6-	PIPE RAIL FOR GUARDRAIL	LF	75.000
	0536- 7- 2	SPECIAL GUARDRAIL POST- SPECIAL STEEL POST FOR CONCRETE STRUCTURE MOUNT	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	176.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	322.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	621.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	2.399
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	516.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	258.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.723
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.473
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	16.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	16.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44113415201)	LS	1.000
<b>Section 0002 Signing</b>				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	22.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	11.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	30.000

**Call Order: 001 Proposal: E56A2**

ALT	Item	Description	Unit	Quantity
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	10.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	6.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	13.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	10.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	621.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	175.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44113415201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	431.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.473
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	13.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	57.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.059
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	1,986.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	887.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	2.399
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.047
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.723
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	1.873
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	0.080
<b>Section 0003 Signalization</b>				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	370.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	250.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	140.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	270.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	150.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	8.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	3.000
	0650- 2-109	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT-FURNISH & INSTALL, BACKPLATE- FLEXIBLE REQUIRED	EA	18.000

**Call Order: 001 Proposal: E56A2**

ALT	Item	Description	Unit	Quantity
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	8.000
	0653- 1- 60	PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN	AS	5.000
	0660- 1-600	LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN	EA	6.000
	0660- 3- 11	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL CABINET EQUIPMENT	EA	2.000
	0660- 3- 12	VEHICLE DETECTION SYSTEM- MICROWAVE, FURNISH & INSTALL, ABOVE GROUND EQUIPMENT	EA	8.000
	0663- 1-111	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, CABINET ELECTRONICS	EA	2.000
	0663- 1-112	SIGNAL PRIORITY AND PREEMPTION SYSTEM, F&I, OPTICAL, DETECTOR	EA	2.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	8.000
	0665- 1- 50	PEDESTRIAN DETECTOR, ADJUST/MODIFY ON EXISTING POLE	EA	1.000
	0665- 1- 60	PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN	EA	5.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0670- 5-400	TRAFFIC CONTROLLER ASSEMBLY, MODIFY	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	1.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	8.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	9.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	4.000
	0700- 5- 60	INTERNALLY ILLUMINATED SIGN, REMOVE	EA	4.000