

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05210707	Call Order: 002	Proposal: E56A4	District:05
Counties:	BREVARD			
Road Name:	SR 520			
Limits:	70100000			
Project(s):	44395715201(*)	Federal Aid No: N/A		
Total Roadway Length:	2.710 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	07/07/21	
Total Proposal Length:	2.710 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Acquisition Days	

Proposal Budget Estimate: \$3,720,875.00

Please read the full advertisement

Description:

The improvements under this contract consist of milling & resurfacing, shoulder treatment, guardrail, and signing and pavement markings on SR 520 from the Orange County Line to west of SR 524 approximately 2.748 miles in Brevard County.

PREQUALIFICATION REQUIRED

Call Order: 002 Proposal: E56A4

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44395715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44395715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,720.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	411.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	411.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	39,491.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	120.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	2.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	376.000
	0102-115-	TYPE III BARRICADE	ED	100.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	480.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	480.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.160
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.160
	0104- 10- 3	SEDIMENT BARRIER	LF	625.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	149.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	70.000
	0107- 1-	LITTER REMOVAL	AC	178.780
	0107- 2-	MOWING	AC	178.780
	0110- 1- 1	CLEARING & GRUBBING (44395715201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44395715201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	47.000
	0120- 1-	REGULAR EXCAVATION	CY	1.900
	0120- 6-	EMBANKMENT	CY	2.700

Call Order: 002 Proposal: E56A4

ALT	Item	Description	Unit	Quantity
	0286- 1-	TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS	SY	44.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	37,460.000
	0327- 70- 20	MILLING EXISTING ASPHALT PAVEMENT, 3 3/4" AVG DEPTH	SY	77,046.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	15,803.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	4,471.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	15.700
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	36.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	196.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	230.000
	0425- 1-705	INLETS, GUTTER, TYPE S, PARTIAL	EA	4.000
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	92.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	150.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	454.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	13.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, APPROACH TL-3	EA	2.000
	0536- 8-123	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-002, TRAILING	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	467.000
	0536- 85- 26	GUARDRAIL END TREATMENT- TYPE CRT	EA	1.000
	0544- 3- 1	CRASH CUSHION, TL-3, NARROW	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,041.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,279.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	6.005
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.059
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	24.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.405
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.424
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	68.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.411
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.196
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44395715201)	LS	1.000
Section 0002 Signing				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	95.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	68.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	3.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000

Call Order: 002 Proposal: E56A4

ALT	Item	Description	Unit	Quantity
	0695- 7-162	TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT	EA	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	1.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	17.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	7.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	11.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	30.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	2.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	4.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	2.000
	0700- 3-501	SIGN PANEL, RELOCATE, UP TO 12 SF	EA	5.000
	0701- 18-101	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, WHITE, SOLID, 6"	GM	5.041
	0701- 18-201	PROFILED THERMOPLASTIC, STANDARD- ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	4.091
	0705- 11- 2	DELINEATOR, NON-FLEXIBLE	EA	14.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,060.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44395715201)	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	63.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.445
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	68.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.601
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.059
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	5.444
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	1.173
	0711- 15-231	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6"	GM	0.212
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	377.000
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.143
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.143
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.143