

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05211005 Call Order: 006 Proposal: E5V96-R0 District:05

Counties: LAKE, ORANGE

Road Name: Desilt & Video

Limits: Midpoint

Project(s): 42917627216(*)

Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	365
Total Bridge Length:	0.000 Miles	Letting Date:	10/05/21
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$501,342.00

Please read the full advertisement

Description:

FDOT District 5
 Proposal ID No: E5V96
 Financial Project No.: 429176-2-72-16
 Fiscal Year: 2022
 Counties: Lake, Orange
 Calendar Days: 365

This is a Work Document driven Contract with a budgetary ceiling of \$501,342.00. This Contract includes an option for 2 renewals at 12 months each.

Intent:

The work under this Contract consists of desilting and video inspection of storm water pipes, box culverts, and other drainage structures in various locations within Department rights of way, Department owned easements or other Department owned property in Lake and Orange Counties.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

Call Order: 006 Proposal: E5V96-R0

ALT	Item	Description	Unit	Quantity
Section 0001 CLEAN DRAINAGE STRUCTURES (LF)				
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	50.000
	E425- 73- 1	CLEANING MANHOLES AND INLETS (MECHANICAL)	EA	30.000
	E430- 94- 1	DESILT PIPE, 0 to 24"	LF	56,550.000
	E430- 94- 2	DESILT PIPE, 25-36"	LF	13,252.000
	E430- 94- 3	DESILT PIPE, 37-48"	LF	5,367.000
	E430- 94- 4	DESILT PIPE, 49-60"	LF	2,800.000
	E430- 94- 5	DESILT PIPE, 61" OR GREATER	LF	450.000
	E432- 4-	STORM SEWER INSPECTION (VIDEO CAMERA)	LF	78,450.000