Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 05210908 Call Order: 007 Proposal: E5V92 District:05

Counties: LAKE, ORANGE
Road Name: DRAINAGE REPAIR

Limits: Midpoint

Project(s): 42917627215(*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 160
Total Bridge Length: 0.000 Miles Letting Date: 09/08/21

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A
Aquis/Flexible Start Time: 14

Proposal Budget Estimate: \$1,308,180.00

Please read the full advertisement

Description: FDOT District 5

Proposal ID No.: E5V92

Financial Project No.: 429176-2-72-15

Fiscal Year: 2022 Counties: Lake, Orange Calendar Days: 160 Lead Time: 14 Days

This is a Maintenance Pay Item Contract.

The work under this Contract consists of desilting, video, and pipe lining; cleaning manholes and inlets; and pipe repair in various locations in Lake and Orange Counties.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of drainage repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

		Call Order: 007 Proposal: E5V92		
ALT	Item	Description	Unit	Quantity
Section	0001 REPAIR/R	EPLACE STRM-SIDE-CROSS DRAIN(LF)		
	0101- 1-	MOBILIZATION (0)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 4-10	REMOVAL OF EXISTING CONCRETE	SY	3.000
	0120- 6-	EMBANKMENT	CY	2.000
	0160- 4-	TYPE B STABILIZATION	SY	6.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	6.000
	0334- 1-53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	0.800
	0337- 7-83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76 -22	TN	0.500
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	1.000
	0430-518-130	STRAIGHT CONCRETE ENDWALLS, 18", SINGLE, 45 DEGREES, ROUND	EA	1.000
	0520- 1-10	CONCRETE CURB & GUTTER, TYPE F	LF	10.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	5.600
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	12.000
	E431- 1-21	PIPE LINER, CURED IN PLACE, 0-24"	LF	6,000.000
	E431- 1-22	PIPE LINER, CURED IN PLACE, 25-36"	LF	3,251.000
	E431- 1-23	PIPE LINER, CURED IN PLACE, 37-48"	LF	386.000
	E431- 1-24	PIPE LINER, CURED IN PLACE, 49-60"	LF	500.000