

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	05220607	Call Order: 004	Proposal: E54B8	District:05
Counties:	LAKE			
Road Name:	SR25			
Limits:	11200000			
Project(s):	43705615201(*)	Federal Aid No: N/A		
Total Roadway Length:	2.400 Miles	Contract Days:	280	
Total Bridge Length:	0.000 Miles	Letting Date:	06/07/22	
Total Proposal Length:	2.400 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 LEAD	

Proposal Budget Estimate: \$2,502,482.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of corridor lighting and other incidental work along SR 25 (US 27) from US 192 to Greater Groves Blvd/Golden Eagle Blvd, in Lake County.

**PREQUALIFICATION REQUIRED**

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

**Call Order: 004 Proposal: E54B8**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1-	MOBILIZATION (43705615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43705615201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43705615201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	11,480.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,200.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,034.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	280.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	560.000
	0104- 10- 3	SEDIMENT BARRIER	LF	3,287.000
	0107- 1-	LITTER REMOVAL	AC	338.420
	0107- 2-	MOWING	AC	217.680
	0110- 1- 1	CLEARING & GRUBBING (43705615201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	105.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	105.000
	0527- 2-	DETECTABLE WARNINGS	SF	16.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43705615201)	LS	1.000
<b>Section 0002 Lighting</b>				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	2.328
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	17,842.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	6,155.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	280.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	149.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	27.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	3.000
	0639- 8-100	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), DUKE (DO NOT BID) (43705615201)	LS	1.000
	0639- 8-110	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), SECO (DO NOT BID) (43705615201)	LS	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	3.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	60,817.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	21,360.000
	0715- 4- 13	LIGHT POLE COMPLETE, FURNISH & INSTALL STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT	EA	99.000
	0715- 4-854	LIGHT POLE COMPLETE, F&I UTILITY CONFLICT POLE, SPECIAL FOUND, 40' HT, PROJECT 437056-1-52-01	EA	13.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	3.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	112.000