

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05221101 Call Order: 007 Proposal: E55B4 District:05

Counties: BREVARD

Road Name: I-95 BRIDGE REHAB; BRIDGES 700162 CARTER CANAL;700050

Limits: 70220000

Project(s): 44942515201(*)

Federal Aid No: N/A

Total Roadway Length:	0.052 Miles	Contract Days:	170
Total Bridge Length:	0.009 Miles	Letting Date:	11/01/22
Total Proposal Length:	0.061 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$882,687.00

Please read the full advertisement

Description:

The improvements under this contract consist of desilting and shotcrete rehabilitation of concrete box culverts (Bridge Nos. 700162 and 700050) along SR 9 (I-95) and removal of sediment buildup and vegetation adjacent to the culvert openings, in Brevard County.

PREQUALIFICATION REQUIRED

Call Order: 007 Proposal: E55B4

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0401- 70- 7	RESTORE SPALLED AREAS, SHOTCRETE	CF	2,010.400
	0430-950-	DESILTING CONCRETE BOX CULVERT	CY	1,101.900
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44942515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44942515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	3,780.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	9,290.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	380.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	872.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	760.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	760.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	55.000
	0104- 12-	STAKED TURBIDITY BARRIER- NYLON REINFORCED PVC	LF	105.000
	0110- 1- 1	CLEARING & GRUBBING (44942515201)	LS	1.000
	0120- 5-	CHANNEL EXCAVATION	CY	364.400
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44942515201)	LS	1.000