

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05230404	Call Order: 008	Proposal: E58B9	District:05
Counties:	MARION, SUMTER			
Road Name:	I-75			
Limits:	18130000			
Project(s):	45050615201	Federal Aid No: N/A		
Project(s):	45050715201(*)	Federal Aid No: N/A		
Total Roadway Length:	67.278 Miles	Contract Days:	160	
Total Bridge Length:	0.000 Miles	Letting Date:	04/04/23	
Total Proposal Length:	67.278 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	120 Days Lead	
Proposal Budget Estimate:	\$2,549,746.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Dynamic Message Sign (DMS) deployment on State Road 93A (I-75) from MP 0.000 in Marion County to MP 28.996 in Sumter County, a length of approximately 67.278 miles.

PREQUALIFICATION REQUIRED

Call Order: 008 Proposal: E58B9

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45050615201)	LS	1.000
	0101- 1-	MOBILIZATION (45050715201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45050615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45050715201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	778.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	762.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	12.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	155.000
	0110- 1- 1	CLEARING & GRUBBING (45050615201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (45050715201)	LS	1.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	20.000
Section 0002 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	67.263
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	5.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	10,919.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	649.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	575.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	11,893.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	24.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	102.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	4.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	10.000

Call Order: 008 Proposal: E58B9

ALT	Item	Description	Unit	Quantity
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	10.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	1.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	4.000
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	120.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	21.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	16.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	4,002.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	117.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	10.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	3.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	1.000
	0639- 8-146	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), OCALA ELECTRIC UTILITY (DO NOT BID) (45050615201)	LS	1.000
	0641- 2- 11	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II PEDESTAL	EA	5.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	2.000
	0676- 2-143	ITS CABINET, FURNISH & INSTALL, BASE MOUNT, 334, 24" W X 66" H X 30" D	EA	5.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	5.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	5.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	5.000
	0700- 9-137	WALK-IN DYNAMIC MESSAGE SIGN, FURNISH & INSTALL- WITH UPS FULL COLOR, 201-300 SF	EA	5.000
	0700- 10-123	DMS SUPPORT STRUCTURE, CANTILEVER, 31-40 FT	EA	5.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45050615201)	LS	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45050715201)	LS	1.000