

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05231205 Call Order: 004 Proposal: E54C7 District:05
Counties: BREVARD

Road Name: DRAINAGE REPAIR
Limits: Midpoint

Project(s): 41232657234(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	12/05/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$400,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID No: E54C7
Project No: 412326-5-72-34
Fiscal Year: 2024

Counties: Brevard
Contract Calendar Days: 180
Lead Time: 14 Calendar Days

INTENT AND SCOPE:

The work under this Contract consists of storm water drainage repair in various locations in Brevard County. Work includes culvert pipe replacement, installation of pipe liner, mitered end sections repair, sidewalk repair, ditch reshaping, and driveway surface restoration.

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 004 Proposal: E54C7

ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0120- 3-	LATERAL DITCH EXCAVATION	CY	37.000
	0285-703-	OPTIONAL BASE, BASE GROUP 03	SY	132.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	22.200
	0430- 96-	DRAINAGE PIPE REPAIR- CONCRETE COLLAR AT JOINT	EA	4.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	942.000
	0430-175-124	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD	LF	16.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	1.000
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	6.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	49.200
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	23.300
	0527- 2-	DETECTABLE WARNINGS	SF	10.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	313.200
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	15.000
	E431- 1- 21	PIPE LINER, CURED IN PLACE, 0-24"	LF	205.000