

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting:	05230209	Call Order: 010	Proposal: E5X65	District:05
Counties:	VOLUSIA			
Road Name:	Drainage Outfall Repair			
Limits:	Midpoint			
Project(s):	42798617232(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	280	
Total Bridge Length:	0.000 Miles	Letting Date:	02/09/23	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$1,800,000.00

Please read the full advertisement

**Description:**

FDOT District 5  
Proposal ID No.: E5X65  
Financial Project No.: 427986-1-72-32  
Fiscal Year: 2023

Counties: Volusia  
Contract Calendar Days: 280  
Lead Time: 14 Days

This is a Maintenance Pay Item Project.

**INTENT AND SCOPE:**

The work under this contract consists of stormwater pipe lining and repair of SR A1A outfall pipe at Driftwood Ave in Daytona Beach, Volusia County.

**EXPERTISE REQUIRED:**

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 010 Proposal: E5X65**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	27.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	453.330
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	1,966.300
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	186.520
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	186.520
	0425- 5-	MANHOLE, ADJUST	EA	2.000
	0425- 74- 2	MANHOLES & INLETS CLEANING & SEALING, >10'	EA	5.000
	0430- 95- 5	OUTFALL BARNACLE REMOVAL, 61" AND GREATER	LF	425.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	123.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6.200
	0580- 1- 1	LANDSCAPE COMPLETE- SMALL PLANTS	LS	1.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	3.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE	LS	1.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	25.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	2.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.039
	E431- 1- 25	PIPE LINER, CURED IN PLACE, 61" AND GREATER	LF	2,937.000