

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05230104	Call Order: 001	Proposal: E54B0	District:05
Counties:	VOLUSIA			
Road Name:	SJR2C LOOP TRAIL			
Limits:	Midpoint			
Project(s):	43986525201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	230	
Total Bridge Length:	0.000 Miles	Letting Date:	01/04/23	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days Lead	

Proposal Budget Estimate: \$1,369,688.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of shared use path construction for the St. Johns River to Sea (SJR2C) Loop Trail on S. Palmetto Avenue from Ridge Boulevard to Beville Road, approximately 1.2 miles in Volusia County.

PREQUALIFICATION REQUIRED

Call Order: 001 Proposal: E54B0

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43986525201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43986525201)	LS	1.000
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43986525201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	7,360.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	2,983.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	2,094.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	4,600.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	3,348,110.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	460.000
	0104- 10- 3	SEDIMENT BARRIER	LF	6,621.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	28.000
	0107- 1-	LITTER REMOVAL	AC	16.540
	0107- 2-	MOWING	AC	14.760
	0110- 1- 1	CLEARING & GRUBBING (43986525201)	LS	1.000
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.410
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	4,280.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	17.000
	0120- 1-	REGULAR EXCAVATION	CY	657.000
	0120- 6-	EMBANKMENT	CY	238.000
	0425- 1-521	INLETS, DT BOT, TYPE C,<10'	EA	2.000
	0425- 1-525	INLETS, DITCH BOTTOM, TYPE C, PARTIAL	EA	4.000
	0425- 1-565	INLETS, DITCH BOTTOM, TYPE F, PARTIAL	EA	3.000

Call Order: 001 Proposal: E54B0

ALT	Item	Description	Unit	Quantity
	0425- 2- 63	MANHOLES, P-8, PARTIAL	EA	1.000
	0425- 6-	VALVE BOXES, ADJUST	EA	33.000
	0425- 10-	YARD DRAIN	EA	1.000
	0430-175-112	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 12"S/CD	LF	3.000
	0430-175-218	PIPE CULVERT,OPTIONAL MATERIAL,OTHER-ELIP/ARCH, 18"S/CD	LF	34.000
	0430-982-121	MITERED END SECTION, OPTIONAL ROUND, 12" CD	EA	2.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	117.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	68.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	5,846.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,482.000
	0527- 2-	DETECTABLE WARNINGS	SF	536.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	6,184.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43986525201)	LS	1.000
Section 0002 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	22.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	17.000
	0700- 3-401	SIGN PANEL, INSTALL, UP TO 12 SF	EA	4.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.009
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.004
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	996.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	172.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	170.000
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	202.000