

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05230606	Call Order: 011	Proposal: E58B1	District:05
Counties:	ORANGE			
Road Name:	SR-400			
Limits:	75280000			
Project(s):	44891515201(*)	Federal Aid No: N/A		
Total Roadway Length:	0.600 Miles	Contract Days:	750	
Total Bridge Length:	0.059 Miles	Letting Date:	06/06/23	
Total Proposal Length:	0.659 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	90 LEAD	

Proposal Budget Estimate: \$21,209,094.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of adding an auxiliary lane to SR 400, ramp widening from one lane to two lanes, ramp bridge widening over SR 400, widening and new shoulders on SR 400, widening on SR 528, milling and resurfacing westbound SR 400 and eastbound SR 528, and a new ITS line on SR 400 and SR 528 from north of the SR 400 and SR 528 interchange to the east of the SR 400 and SR 528 interchange approximately 0.3 miles in Orange County.

PREQUALIFICATION REQUIRED

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (44891515201 750180)	LS	1.000
	0400- 2- 10	CONCRETE CLASS II, APPROACH SLABS	CY	60.900
	0400- 4- 4	CONCRETE CLASS IV, SUPERSTRUCTURE	CY	233.900
	0400- 4- 5	CONCRETE CLASS IV, BRIDGE SUBSTRUCTURE	CY	32.800
	0400- 4- 25	CONCRETE CLASS IV, MASS, SUBSTRUCTURE	CY	201.000
	0400- 7- 1	BRIDGE DECK GROOVING	SY	935.000
	0400-143-	CLEANING & COATING CONCRETE SURFACE, CLASS 5	SF	5,198.000
	0400-147-	COMPOSITE NEOPRENE PADS	CF	11.400
	0415- 1- 4	REINFORCING STEEL - BRIDGE SUPERSTRUCTURE	LB	59,752.000
	0415- 1- 5	REINFORCING STEEL- BRIDGE SUBSTRUCTURE	LB	47,223.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	11,688.000
	0450- 2- 45	PREST BEAMS: FLORIDA-I BEAM 45"	LF	911.000
	0450- 82-	BEAM REPAIR	LF	56.000
	0455- 34- 3	PRESTRESSED CONCRETE PILING, 18" SQ	LF	1,050.000
	0455- 34- 5	PRESTRESSED CONCRETE PILING, 24" SQ	LF	1,875.000
	0455-143- 3	TEST PILES-PRESTRESSED CONCRETE,18" SQ	LF	320.000
	0455-143- 5	TEST PILES-PRESTRESSED CONCRETE,24" SQ	LF	405.000
	0458- 1- 11	BRIDGE DECK EXPANSION JOINT, NEW CONSTRUCTION, F&I POURED JOINT WITH BACKER ROD	LF	274.000
	0521- 5- 14	CONCRETE TRAFFIC RAILING- BRIDGE, 42" SINGLE-SLOPE	LF	734.000
	0524- 2- 2	CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4"	SY	962.000

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	2,198.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	12.000
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44891515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44891515201)	LS	1.000
	0102- 2-200	SPECIAL DETOUR- TEMPORARY PAVEMENT (44891515201)	LS	1.000
	0102- 2-300	SPECIAL DETOUR- TEMPORARY EARTHWORK/BASE (44891515201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	9.400
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	9,264.000
	0102- 30-	TEMPORARY HIGHWAY LIGHTING (44891515201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	23,428.000
	0102- 62- 12	BARRIER MOUNTED WORK ZONE SIGN- INDEX 700-012	ED	54,304.000
	0102- 71- 15	TEMPORARY BARRIER, F&I, ANCHORED	LF	2,138.000
	0102- 71- 16	TEMPORARY BARRIER, F&I, FREE STANDING	LF	274.000
	0102- 71- 25	TEMPORARY BARRIER, RELOCATE, ANCHORED	LF	3,089.000
	0102- 71- 26	TEMPORARY BARRIER, RELOCATE, FREE STANDING	LF	179.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	128,214.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	397.000
	0102- 89- 1	TEMPORARY CRASH CUSHION, REDIRECTIVE OPTION	LO	13.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	10,029.000
	0102-115-	TYPE III BARRICADE	ED	2,816.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	1,714.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	1,714.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.277
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.205
	0104- 10- 3	SEDIMENT BARRIER	LF	6,865.000
	0104- 15-	SOIL TRACKING PREVENTION DEVICE	EA	2.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	15.000
	0107- 1-	LITTER REMOVAL	AC	921.850
	0107- 2-	MOWING	AC	799.730
	0108- 1-	MONITOR EXISTING STRUCTURES- INSPECTION AND SETTLEMENT MONITORING (44891515201)	LS	1.000
	0110- 1- 1	CLEARING & GRUBBING (44891515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	152.000
	0110- 12- 1	HYDRODEMOLITION, REMOVAL OF DECK SURFACE	SY	257.000
	0120- 1-	REGULAR EXCAVATION	CY	22,212.000
	0120- 6-	EMBANKMENT	CY	33,982.000
	0160- 4-	TYPE B STABILIZATION	SY	24,672.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	2,986.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	5,849.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	12,308.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	141.000
	0327- 70- 8	MILLING EXISTING ASPHALT PAVEMENT, 2 1/2" AVG DEPTH	SY	1,001.000
	0327- 70- 11	MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH	SY	7,461.000

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	3,567.000
	0334- 1- 12	SUPERPAVE ASPHALTIC CONC, TRAFFIC B	TN	238.400
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	2,023.300
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	887.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	2,124.100
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	920.100
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	31.200
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	120.000
	0425- 1-549	INLETS, DT BOT, TYPE D, MODIFY	EA	1.000
	0425- 1-701	INLETS, GUTTER, TYPE S, <10'	EA	10.000
	0425- 1-702	INLETS, GUTTER, TYPE S, >10'	EA	3.000
	0425- 1-703	INLETS, GUTTER, TYPE S, J BOTTOM <10'	EA	1.000
	0425- 1-704	INLETS, GUTTER, TYPE S, J BOTTOM, >10'	EA	1.000
	0430-174-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD	LF	55.000
	0430-175-118	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"S/CD	LF	674.000
	0430-175-124	PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"S/CD	LF	754.000
	0430-175-130	PIPE CULVERT, OPT MATERIAL, ROUND, 30"S/CD	LF	145.000
	0430-530-100	STRAIGHT CONCRETE ENDWALLS, 30", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0430-530-200	STRAIGHT CONCRETE ENDWALLS, 30", DOUBLE, 0 DEGREES, ROUND	EA	1.000
	0430-611-033	U-ENDWALL, INDEX 261/430-011, BAFFLES, 1:6 SLOPE, 30"PIPE	EA	1.000
	0430-611-129	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 24"PIPE	EA	2.000
	0430-611-225	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:3 SLOPE, 18"PIPE	EA	1.000
	0430-611-325	U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:2 SLOPE, 18"PIPE	EA	2.000
	0430-830-	PIPE FILLING AND PLUGGING- PLACE OUT OF SERVICE	CY	5.300
	0430-982-125	MITERED END SECTION, OPTIONAL ROUND, 18" CD	EA	1.000
	0430-984-129	MITERED END SECTION, OPTIONAL ROUND, 24" SD	EA	2.000
	0520- 6-	SHOULDER GUTTER- CONCRETE	LF	2,986.000
	0521- 8- 7	CONCRETE BARRIER, WITH JUNCTION SLAB, 36" SINGLE SLOPE	LF	420.000
	0521- 72- 40	SHOULDER CONCRETE BARRIER, 38" OR 44" HEIGHT	LF	19.000
	0521- 72- 56	SHOULDER CONCRETE BARRIER, 56" PIER PROTECTION BARRIER/CRASH WALL	LF	397.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	2.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	2,685.000
	0536- 1- 3	GUARDRAIL- ROADWAY, DOUBLE FACE	LF	137.000
	0536- 8-112	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, APPROACH TL-3	EA	3.000
	0536- 8-113	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I- INDEX 536-001, TRAILING	EA	4.000
	0536- 73-	GUARDRAIL REMOVAL	LF	2,977.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	3.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	2.000
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	0.436
	0548- 12-	RETAINING WALL SYSTEM, PERMANENT, EXCLUDING BARRIER	SF	6,216.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	62,830.000

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
	0630- 2- 16	CONDUIT, FURNISH & INSTALL, EMBEDDED CONCRETE BARRIERS AND TRAFFIC RAILINGS	LF	1,524.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	567.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.487
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.939
	0710- 11-103	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE MARKINGS, 12"	GM	0.057
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	788.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	1.966
	0710- 11-133	PAINTED PAVEMENT MARKING, STANDARD, WHITE, 3'-9' SKIP DROP LINE AND APPROACH TO TOLL PLAZA, 12" WIDE,	GM	0.508
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.839
	0710- 11-202	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.117
	0999- 20- 1	DISPUTES REVIEW BOARD, MEETING- DO NOT BID	DA	8.000
	0999- 20- 2	DISPUTES REVIEW BOARD, HEARING- DO NOT BID	EA	1.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44891515201)	LS	1.000
Section 0003 Signing				
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	1.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	13.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	2.000
	0700- 1- 32	SINGLE POST SIGN, F&I BRIDGE MOUNT INDEX 11870/700-012, 12-20 SF	AS	4.000
	0700- 1- 50	SINGLE POST SIGN, RELOCATE	AS	1.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	13.000
	0700- 2- 14	MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF	AS	1.000
	0700- 2- 15	MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF	AS	2.000
	0700- 2- 16	MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF	AS	1.000
	0700- 2- 60	MULTI- POST SIGN, REMOVE	AS	2.000
	0700- 3-202	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 12-20 SF	EA	1.000
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	2.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	1.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	2.000
	0700- 3-209	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 401-500 SF	EA	1.000
	0700- 3-254	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 301-400 SF WITH LIGHTING, PROJECT 448915-1-52-01	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0700- 3-605	SIGN PANEL, REMOVE, 51-100 SF	EA	1.000
	0700- 3-609	SIGN PANEL, REMOVE, 401-500 SF	EA	1.000
	0700- 3-611	SIGN PANEL, REMOVE, 601 SF AND GREATER	EA	1.000
	0700- 3-628	SIGN PANEL, REMOVE PANEL, 301-400 SF WITH LIGHTING	EA	2.000
	0700- 4-114	OVERHEAD STATIC SIGN STRUCTURE, FURNISH & INSTALL, CANTILEVER, 41-50 FT	EA	3.000

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
	0700- 4-611	OVERHEAD STATIC SIGN STRUCTURE, SHALLOW FOUNDATION REMOVAL, CANTILEVER	EA	3.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	39.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	737.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44891515201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.333
	0711- 11-103	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR INTERCHANGE MARKINGS	GM	0.057
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	822.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	1.364
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	1.907
	0711- 15-133	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 12"- APPROACH TO TOLL PLAZA OR 3-9 LANE DROP	GM	0.506
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.774
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.070
	0713-103-131	PERMANENT TAPE, WHITE, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.061
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.070
	0713-103-331	PERMANENT TAPE, BLACK, SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.061
Section 0004 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	5,620.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	572.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	95.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	55.000
	0635- 3- 13	JUNCTION BOX, FURNISH & INSTALL, EMBEDDED	EA	8.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	348.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	38,762.000
	0715- 1- 14	LIGHTING CONDUCTORS, F&I, INSULATED, NO 1 TO NO 0	LF	175.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	2,772.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	1.000
	0715- 19- 13	HIGH MAST LIGHT POLE, FURNISH AND INSTALL, 120'	EA	1.000
	0715- 19- 61	HIGH MAST LIGHT POLE, REMOVE POLE- FOUNDATION REMAINS	EA	2.000
	0715- 61-300	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 40' MOUNTING HEIGHT, 0' ARM LENGTH	EA	22.000
	0715- 61-500	LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 50' MOUNTING HEIGHT, 0' ARM LENGTH	EA	15.000

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL	EA	37.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	1.000
Section 0005 Intelligent Transportation System				
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	0.300
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	12.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	4,501.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,784.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	180.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	1,744.000
	0633- 1-122	FIBER OPTIC CABLE, F&I, UNDERGROUND,13-48 FIBERS	LF	7,519.000
	0633- 1-123	FIBER OPTIC CABLE, F&I, UNDERGROUND,49-96 FIBERS	LF	7,474.000
	0633- 1-620	FIBER OPTIC CABLE, REMOVE, UNDERGROUND	LF	16,101.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	310.000
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	12.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	6.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	28.000
	0633- 3- 13	FIBER OPTIC CONNECTION HARDWARE, F&I, PRETERMINATED CONNECTOR ASSEMBLY	EA	54.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	2.000
	0633- 3- 17	FIBER OPTIC CONNECTION HARDWARE, F&I, CONNECTOR PANEL	EA	5.000
	0633- 3- 51	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE ENCLOSURE	EA	4.000
	0633- 3- 52	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY SPLICE TRAY	EA	6.000
	0633- 3- 56	FIBER OPTIC CONNECTION HARDWARE, ADJUST/MODIFY PATCH PANEL	EA	1.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	750.000
	0633- 8- 1	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL	LF	494.000
	0633- 8- 6	MULTI-CONDUCTOR COMMUNICATION CABLE, REMOVE	LF	300.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	12.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	16.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	3.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	3,589.000
	0639- 2- 6	ELECTRICAL SERVICE WIRE, REMOVE	LF	3,833.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	6.000
	0639- 3- 60	ELECTRICAL SERVICE DISCONNECT, REMOVE- POLE OR CABINET TO REMAIN	EA	4.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	4.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	4.000
	0641- 2- 14	PRESTRESSED CONCRETE POLE, F&I, TYPE P-IV	EA	1.000
	0641- 2- 60	PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE	EA	4.000
	0641- 2- 70	PRESTRESSED CONCRETE POLE, SHALLOW POLE REMOVAL- POLE 30' AND GREATER	EA	2.000

Call Order: 011 Proposal: E58B1

ALT	Item	Description	Unit	Quantity
	0641- 3-163	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 63'	EA	1.000
	0641- 3-169	CONCRETE CCTV POLE, FURNISH & INSTALL WITH LOWERING DEVICE, 69'	EA	1.000
	0641- 3-700	CONCRETE CCTV POLE, SHALLOW POLE REMOVAL	EA	2.000
	0660- 3- 42	VEHICLE DETECTION SYSTEM - MICROWAVE, RELOCATE, ABOVE GROUND EQUIPMENT	EA	1.000
	0676- 2-400	ITS CABINET, RELOCATE	EA	3.000
	0676- 2-500	ITS CABINET- ADJUST/MODIFY	EA	4.000
	0676- 3- 10	SMALL EQUIPMENT ENCLOSURE, FURNISH AND INSTALL, LESS THAN 10"W X 13"H X 11" D	EA	1.000
	0682- 1-133	ITS CCTV CAMERA, F&I, DOME ENCLOSURE - NON-PRESSURIZED, IP, HIGH DEFINITION	EA	2.000
	0700- 8-600	FRONT ACCESS DYNAMIC MESSAGE SIGN, REMOVE	EA	1.000
	0700- 9-500	WALK-IN DYNAMIC MESSAGE SIGN, RELOCATE	EA	1.000
	0700- 10-124	DMS SUPPORT STRUCTURE, CANTILEVER, 41-50 FT	EA	1.000
	0700- 10-600	DMS SUPPORT STRUCTURE, REMOVE	EA	1.000