

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

---

Letting: 05231107      Call Order: 006      Proposal: E55C1      District:05  
Counties: OSCEOLA

Road Name: Tennessee Outfall Repair  
Limits: Midpoint

Project(s): 41232657237(\*)      Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	11/07/23
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$800,200.00

Please read the full advertisement

**Description:**

FDOT District 5  
Proposal ID No.: E55C1  
Financial project No.: 412326-5-72-37  
Fiscal Year: 2024  
County: Osceola  
Contract Calendar Days: 90  
Lead Time: 30 Days

This is a Maintenance Pay Item Contract.

**Intent:**

The work under this Contract includes the reconstruction of the Tennessee Outfall; installation of culverts, drainage structures, embankment, sodding and fencing.

**Experience:**

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

**Call Order: 006 Proposal: E55C1**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 OUTFALL DITCHES, CLEAN AND REPAIR (LF)</b>				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	596.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	98.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	0.740
	0107- 2-	MOWING	AC	0.740
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	21.000
	0120- 1-	REGULAR EXCAVATION	CY	72.000
	0120- 4-	SUBSOIL EXCAVATION	CY	1,286.000
	0120- 6-	EMBANKMENT	CY	7,142.000
	0425- 1-551	INLETS, DT BOT, TYPE E, <10'	EA	1.000
	0425- 2- 71	MANHOLES, J-7, <10'	EA	1.000
	0430-175-136	PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD	LF	8.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	243.000
	0430-175-154	PIPE CULVERT, OPT MATERIAL, ROUND, 54"S/CD	LF	503.000
	0430-560-100	STRAIGHT CONCRETE ENDWALLS, 60", SINGLE, 0 DEGREES, ROUND	EA	1.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	21.000
	0524- 1- 2	CONCRETE DITCH PAVEMENT, NON REINFORCED, 4"	SY	47.000
	0530- 4- 4	ARTICULATING CONCRETE BLOCK REVETMENT SYSTEM, THICKNESS 4"	SY	68.000
	0550- 10-222	FENCING, TYPE B, 5.1-6.0, W/ VINYL COATING	LF	96.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	4,289.000