

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05240402	Call Order: 003	Proposal: E51F9	District:05
Counties: FLAGLER			
Road Name: SR A1A			
Limits: 73030000			
Project(s): 43912415201(*)	Federal Aid No: N/A		
Total Roadway Length: 3.798 Miles	Contract Days: 260		
Total Bridge Length: 0.000 Miles	Letting Date: 04/02/24		
Total Proposal Length: 3.798 Miles	Contract Execution Days: 10		
	Special Start Date: N/A		
	Aquis/Flexible Start Time: 30 LEAD		

Proposal Budget Estimate: \$6,073,702.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, widening, sidewalks, drainage, and signing and pavement markings along SR A1A from Osprey Drive to north of Mariners Drive in Flagler County.

PREQUALIFICATION REQUIRED

Call Order: 003 Proposal: E51F9

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43912415201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43912415201)	LS	1.000
	0102- 3-	COMMERCIAL MATERIAL FOR TEMPORARY DRIVEWAY MAINTENANCE	CY	351.400
	0102- 4- 1	PEDESTRIAN OR BICYCLE SPECIAL DETOUR (43912415201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	10,320.000
	0102- 61-	BUSINESS SIGN	EA	3.000
	0102- 71- 13	TEMPORARY BARRIER, F&I, LOW PROFILE, CONCRETE	LF	594.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	121,680.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	683,720.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	520.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	548.000
	0104- 1-	ARTIFICIAL COVERINGS /ROLLED EROSION CONTROL PRODUCTS	SY	232.000
	0104- 10- 3	SEDIMENT BARRIER	LF	16,861.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	1.000
	0107- 1-	LITTER REMOVAL	AC	216.430
	0107- 2-	MOWING	AC	216.430
	0110- 1- 1	CLEARING & GRUBBING (43912415201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	2,074.000
	0110- 7- 1	MAILBOX, F&I SINGLE	EA	25.000
	0120- 1-	REGULAR EXCAVATION	CY	1,004.000
	0120- 6-	EMBANKMENT	CY	3,320.000
	0160- 4-	TYPE B STABILIZATION	SY	12,131.000

Call Order: 003 Proposal: E51F9

ALT	Item	Description	Unit	Quantity
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	5,173.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	348.000
	0286- 2-	TURNOUT CONSTRUCTION-ASPHALT/DRIVEWAY BASE- ASPHALT MATERIAL	TN	118.100
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	48,355.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	1,527.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	14,604.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	5,241.300
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,836.700
	0400- 0- 11	CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011	CY	20.500
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	4.000
	0425- 6-	VALVE BOXES, ADJUST	EA	5.000
	0515- 1- 2	PIPE HANDRAIL - GUIDERAIL, ALUMINUM	LF	80.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	1,591.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	1,735.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	1,867.000
	0524- 1- 1	CONCRETE DITCH PAVT, NON REINFORCED, 3"	SY	31.000
	0527- 2-	DETECTABLE WARNINGS	SF	780.000
	0530- 3- 4	RIPRAP, RUBBLE, F&I, DITCH LINING	TN	43.900
	0530- 74-	BEDDING STONE	TN	31.500
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	23,549.000
	0571- 1- 11	PLASTIC EROSION MAT, TURF REINFORCED MAT, TYPE 1	SY	3,382.000
	0639- 8-130	ELECTRICAL POWER SERVICE- CONTRIBUTION IN AID OF CONSTRUCTION (CIAC), FPL (DO NOT BID) (43912415201)	LS	1.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	5,576.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	17.164
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	1,559.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	88.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	283.000
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.415
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	60.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	17.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	9.719
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	229.000
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.159
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43912415201)	LS	1.000
Section 0002 Signing				
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	985.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	120.000

Call Order: 003 Proposal: E51F9

ALT	Item	Description	Unit	Quantity
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	14.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	4.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	1,525.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	6.000
	0654- 2- 18	MIDBLOCK CROSSWALK: REC RAPID FLASHING BEACON, FURNISH/INSTALL- AC, SIGN ASSEMBLY- BACK-BACK ACCESSIBLE DETECTOR	AS	8.000
	0700- 1- 11	SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF	AS	90.000
	0700- 1- 12	SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF	AS	2.000
	0700- 1- 13	SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF	AS	7.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	73.000
	0700-142-131	ENHANCED HIGHWAY SIGN ASSEMBLY, SOLAR POWERED, F&I GROUND MOUNT, W/EDS, UP TO 12 SF OF STATIC SIGN PANELS	EA	6.000
	0704- 1- 2	TUBULAR MARKER, DURABLE, 36" YELLOW POST	EA	12.000
	0705- 10- 1	OBJECT MARKER, TYPE 1	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,248.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	208.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (43912415201)	LS	1.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,499.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	88.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	220.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.415
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	60.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	17.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	229.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.159
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	286.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	48.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	48.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	14.354
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	6.964
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	143.000