

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05240206 Call Order: 003 Proposal: E51F3 District:05

Counties: VOLUSIA

Road Name: SR 15/600 (US 17/92)

Limits: 79040000

Project(s): 44530115201(*)

Federal Aid No: N/A

| | | | |
|------------------------|-------------|----------------------------|----------|
| Total Roadway Length: | 2.852 Miles | Contract Days: | 400 |
| Total Bridge Length: | 0.000 Miles | Letting Date: | 02/06/24 |
| Total Proposal Length: | 2.852 Miles | Contract Execution Days: | 10 |
| | | Special Start Date: | N/A |
| | | Aquis/Flexible Start Time: | 30 |

Proposal Budget Estimate: \$11,729,397.00

Please read the full advertisement

Description:

SR 15/600 (US 17/92) FROM N OF WISCONSIN AVE TO N OF SR15A (TAYLOR RD) - RESURFACING

The Improvements under this Contract consist of milling & resurfacing, base work, shoulder treatment, sidewalk, drainage improvements, curb & gutter, traffic signals, lighting, and signing and pavement markings on SR 15/600 from north of Wisconsin Ave. to north of SR 15A approximately 2.825 miles in Volusia County.

PREQUALIFICATION REQUIRED

Call Order: 003 Proposal: E51F3

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|--|------|------------|
| Section 0001 Roadway | | | | |
| | 0101- 1- | MOBILIZATION (44530115201) | LS | 1.000 |
| | 0102- 1- | MAINTENANCE OF TRAFFIC (44530115201) | LS | 1.000 |
| | 0102- 4- 1 | PEDESTRIAN OR BICYCLE SPECIAL DETOUR (44530115201) | LS | 1.000 |
| | 0102- 14- | TRAFFIC CONTROL OFFICER | HR | 680.000 |
| | 0102- 60- | WORK ZONE SIGN | ED | 41,258.000 |
| | 0102- 74- 1 | CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD | ED | 5,284.000 |
| | 0102- 74- 8 | CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE) | FD | 30,548.000 |
| | 0102- 76- | ARROW BOARD / ADVANCE WARNING ARROW PANEL | ED | 802.000 |
| | 0102- 99- | PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY | ED | 950.000 |
| | 0102-104- | TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION | ED | 2,000.000 |
| | 0102-107- 1 | TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION | ED | 2,000.000 |
| | 0102-115- | TYPE III BARRICADE | ED | 16.000 |
| | 0102-150- 1 | PORTABLE REGULATORY, SIGN | ED | 52.000 |
| | 0102-150- 2 | RADAR SPEED DISPLAY UNIT | ED | 52.000 |
| | 0102-913- 23 | REMOVABLE TAPE, WHITE, 24" STOP BAR | LF | 240.000 |
| | 0102-913- 24 | REMOVABLE TAPE, WHITE, 12" CROSSWALK | LF | 2,854.000 |
| | 0104- 10- 3 | SEDIMENT BARRIER | LF | 4,899.000 |
| | 0104- 18- | INLET PROTECTION SYSTEM | EA | 31.000 |
| | 0107- 1- | LITTER REMOVAL | AC | 310.020 |
| | 0107- 2- | MOWING | AC | 310.020 |

Call Order: 003 Proposal: E51F3

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|---|------|------------|
| | 0110- 1- 1 | CLEARING & GRUBBING (44530115201) | LS | 1.000 |
| | 0110- 4- 10 | REMOVAL OF EXISTING CONCRETE | SY | 1,441.000 |
| | 0110- 7- 1 | MAILBOX, F&I SINGLE | EA | 4.000 |
| | 0120- 1- | REGULAR EXCAVATION | CY | 3,279.000 |
| | 0120- 6- | EMBANKMENT | CY | 2,316.000 |
| | 0160- 4- | TYPE B STABILIZATION | SY | 5,055.000 |
| | 0285-701- | OPTIONAL BASE, BASE GROUP 01 | SY | 629.000 |
| | 0285-704- | OPTIONAL BASE, BASE GROUP 04 | SY | 8,461.000 |
| | 0285-706- | OPTIONAL BASE, BASE GROUP 06 | SY | 2,541.000 |
| | 0286- 1- | TURNOUT CONSTRUCTION/DRIVEWAY BASE- OPTIONAL MATERIALS | SY | 223.000 |
| | 0327- 70- 4 | MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH | SY | 42,755.000 |
| | 0327- 70- 5 | MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH | SY | 359.000 |
| | 0327- 70- 6 | MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH | SY | 8,341.000 |
| | 0327- 70- 7 | MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH | SY | 5,519.000 |
| | 0327- 70- 11 | MILLING EXISTING ASPHALT PAVEMENT, 2 1/4" AVG DEPTH | SY | 7,718.000 |
| | 0327- 70- 15 | MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH | SY | 66,213.000 |
| | 0327- 70- 21 | MILLING EXISTING ASPHALT PAVEMENT, 7" AVG DEPTH | SY | 8,461.000 |
| | 0334- 1- 13 | SUPERPAVE ASPHALTIC CONC, TRAFFIC C | TN | 14,022.000 |
| | 0337- 7- 25 | ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22 | TN | 3,407.200 |
| | 0337- 7- 83 | ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22 | TN | 5,676.200 |
| | 0339- 1- | MISCELLANEOUS ASPHALT PAVEMENT | TN | 17.500 |
| | 0400- 0- 11 | CONCRETE CLASS NS, GRAVITY WALL INDEX 400-011 | CY | 177.000 |
| | 0425- 1-521 | INLETS, DT BOT, TYPE C,<10' | EA | 6.000 |
| | 0425- 1-541 | INLETS, DT BOT, TYPE D, <10' | EA | 5.000 |
| | 0425- 2- 61 | MANHOLES, P-8, <10' | EA | 1.000 |
| | 0425- 6- | VALVE BOXES, ADJUST | EA | 1.000 |
| | 0430-174-118 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 18"SD | LF | 72.000 |
| | 0430-174-124 | PIPE CULVERT, OPTIONAL MATERIAL, ROUND, 24"SD | LF | 30.000 |
| | 0430-175-115 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 15"S/CD | LF | 101.000 |
| | 0430-175-118 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD | LF | 1,513.000 |
| | 0430-175-124 | PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 24"S/CD | LF | 199.000 |
| | 0430-611-125 | U-ENDWALL WITH BAFFLES, INDEX 261/430-011, 1:4 SLOPE, 18"PIPE | EA | 1.000 |
| | 0430-982-123 | MITERED END SECTION, OPTIONAL ROUND, 15" CD | EA | 1.000 |
| | 0430-982-125 | MITERED END SECTION, OPTIONAL ROUND, 18" CD | EA | 1.000 |
| | 0430-984-125 | MITERED END SECTION, OPTIONAL ROUND, 18" SD | EA | 5.000 |
| | 0430-984-129 | MITERED END SECTION, OPTIONAL ROUND, 24" SD | EA | 2.000 |
| | 0515- 1- 2 | PIPE HANDRAIL - GUIDERAIL, ALUMINUM | LF | 393.000 |
| | 0520- 1- 7 | CONCRETE CURB & GUTTER, TYPE E | LF | 414.000 |
| | 0520- 1- 10 | CONCRETE CURB & GUTTER, TYPE F | LF | 433.000 |
| | 0520- 2- 2 | CONCRETE CURB, TYPE B | LF | 69.000 |
| | 0522- 1- | CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK | SY | 4,838.000 |
| | 0522- 2- | CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK | SY | 1,100.000 |
| | 0524- 1- 2 | CONCRETE DITCH PAVEMENT, NON REINFORCED, 4" | SY | 36.000 |
| | 0524- 2- 2 | CONCRETE SLOPE PAVEMENT, NON REINFORCED, 4" | SY | 125.000 |

Call Order: 003 Proposal: E51F3

| ALT | Item | Description | Unit | Quantity |
|-----------------------------|--------------|---|------|-----------|
| | 0527- 2- | DETECTABLE WARNINGS | SF | 1,233.000 |
| | 0530- 3- 4 | RIPRAP, RUBBLE, F&I, DITCH LINING | TN | 48.400 |
| | 0570- 1- 2 | PERFORMANCE TURF, SOD | SY | 2,759.000 |
| | 0706- 1- 3 | RAISED PAVEMENT MARKER, TYPE B | EA | 1,237.000 |
| | 0710- 11-101 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6" | GM | 7.917 |
| | 0710- 11-102 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8" | GM | 0.355 |
| | 0710- 11-123 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12" | LF | 3,078.000 |
| | 0710- 11-124 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18" | LF | 727.000 |
| | 0710- 11-125 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24" | LF | 2,709.000 |
| | 0710- 11-131 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE | GM | 7.089 |
| | 0710- 11-141 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6" | GM | 2.579 |
| | 0710- 11-170 | PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS | EA | 111.000 |
| | 0710- 11-201 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6" | GM | 4.346 |
| | 0710- 11-224 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18" | LF | 873.000 |
| | 0710- 11-231 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6" | GM | 0.116 |
| | 0710- 11-241 | PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6" | GM | 0.770 |
| | 0999- 25- | INITIAL CONTINGENCY AMOUNT, DO NOT BID (44530115201) | LS | 1.000 |
| Section 0002 Signing | | | | |
| | 0700- 1- 11 | SINGLE POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 146.000 |
| | 0700- 1- 12 | SINGLE POST SIGN, F&I GROUND MOUNT, 12-20 SF | AS | 33.000 |
| | 0700- 1- 13 | SINGLE POST SIGN, F&I GROUND MOUNT, 21-30 SF | AS | 5.000 |
| | 0700- 1- 14 | SINGLE POST SIGN, F&I GROUND MOUNT, 31+ SF | AS | 1.000 |
| | 0700- 1- 50 | SINGLE POST SIGN, RELOCATE | AS | 18.000 |
| | 0700- 1- 60 | SINGLE POST SIGN, REMOVE | AS | 45.000 |
| | 0700- 2- 11 | MULTI- POST SIGN, F&I GROUND MOUNT, UP TO 12 SF | AS | 1.000 |
| | 0700- 2- 13 | MULTI- POST SIGN, F&I GROUND MOUNT, 21-30 SF | AS | 5.000 |
| | 0700- 2- 14 | MULTI- POST SIGN, F&I GROUND MOUNT, 31-50 SF | AS | 6.000 |
| | 0700- 2- 15 | MULTI- POST SIGN, F&I GROUND MOUNT, 51-100 SF | AS | 3.000 |
| | 0700- 2- 16 | MULTI- POST SIGN, F&I GROUND MOUNT, 101-200 SF | AS | 3.000 |
| | 0700- 2- 60 | MULTI- POST SIGN, REMOVE | AS | 14.000 |
| | 0700- 3-101 | SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF | EA | 2.000 |
| | 0700- 3-501 | SIGN PANEL, RELOCATE, UP TO 12 SF | EA | 11.000 |
| | 0700- 3-601 | SIGN PANEL, REMOVE, UP TO 12 SF | EA | 1.000 |
| | 0700- 13- 15 | RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5' | EA | 143.000 |
| | 0705- 11- 1 | DELINEATOR, FLEXIBLE TUBULAR | EA | 34.000 |
| | 0706- 1- 3 | RAISED PAVEMENT MARKER, TYPE B | EA | 3,393.000 |
| | 0710- 90- | PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44530115201) | LS | 1.000 |
| | 0711- 11-102 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND | GM | 0.395 |

Call Order: 003 Proposal: E51F3

| ALT | Item | Description | Unit | Quantity |
|------------------------------|--------------|---|------|------------|
| | 0711- 11-123 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT | LF | 10,334.000 |
| | 0711- 11-124 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS | LF | 610.000 |
| | 0711- 11-125 | THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK | LF | 1,235.000 |
| | 0711- 11-141 | THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6" | GM | 2.182 |
| | 0711- 11-160 | THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL | EA | 14.000 |
| | 0711- 11-170 | THERMOPLASTIC, STANDARD, WHITE, ARROW | EA | 205.000 |
| | 0711- 11-224 | THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON | LF | 1,016.000 |
| | 0711- 11-241 | THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6" | GM | 0.733 |
| | 0711- 14-125 | THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK | LF | 3,218.000 |
| | 0711- 14-160 | THERMOPLASTIC, PREFORMED, WHITE, MESSAGE | EA | 27.000 |
| | 0711- 14-170 | THERMOPLASTIC, PREFORMED, WHITE, ARROW | EA | 27.000 |
| | 0711- 15-101 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6" | GM | 5.094 |
| | 0711- 15-131 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM | 3.795 |
| | 0711- 15-201 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6" | GM | 2.856 |
| | 0711- 15-231 | THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SKIP, 6" | GM | 0.117 |
| | 0711- 16-101 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6" | GM | 4.358 |
| | 0711- 16-131 | THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP | GM | 4.006 |
| | 0711- 16-133 | THERMOPLASTIC, STANDARD-OTHER SURFACES WHITE, SKIP, 12"-APPROACH TO TOLL PLAZA OR 3-9 LANE DROP | GM | 0.052 |
| | 0711- 16-201 | THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6" | GM | 2.164 |
| | 0711- 17- 1 | THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN | SF | 430.000 |
| Section 0003 Lighting | | | | |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 1,298.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 1,370.000 |
| | 0630- 2- 14 | CONDUIT, FURNISH & INSTALL, ABOVEGROUND | LF | 50.000 |
| | 0630- 2- 15 | CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT | LF | 201.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 15.000 |
| | 0635- 3- 12 | JUNCTION BOX, FURNISH & INSTALL, MOUNTED | EA | 7.000 |
| | 0639- 1-121 | ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY | AS | 1.000 |
| | 0639- 2- 1 | ELECTRICAL SERVICE WIRE, FURNISH & INSTALL | LF | 69.000 |
| | 0639- 3- 11 | ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT | EA | 1.000 |
| | 0641- 2- 12 | PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE | EA | 1.000 |
| | 0715- 1- 11 | LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR < | LF | 1,873.000 |
| | 0715- 1- 12 | LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6 | LF | 8,718.000 |
| | 0715- 7- 11 | LOAD CENTER, F&I, SECONDARY VOLTAGE | EA | 1.000 |

Call Order: 003 Proposal: E51F3

| ALT | Item | Description | Unit | Quantity |
|-----------------------------------|--------------|--|------|-----------|
| | 0715- 11-125 | LUMINAIRE, F&I, UNDER DECK, WALL MOUNT | EA | 4.000 |
| | 0715- 61-142 | LIGHT POLE COMPLETE, F&I, STANDARD POLE STANDARD FOUNDATION, 30' MOUNTING HEIGHT, 12' ARM LENGTH | EA | 4.000 |
| | 0715-500- 1 | POLE CABLE DISTRIBUTION SYSTEM, FURNISH AND INSTALL, CONVENTIONAL | EA | 4.000 |
| | 0715-500- 3 | POLE CABLE DISTRIBUTION SYSTEM, WALL MOUNT | EA | 4.000 |
| Section 0004 Signalization | | | | |
| | 0611- 1- 1 | ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH | MI | 2.900 |
| | 0611- 2- 1 | ITSFM LOCATION DOCUMENTATION- INTERSECTION | EA | 5.000 |
| | 0630- 2- 11 | CONDUIT, FURNISH & INSTALL, OPEN TRENCH | LF | 1,433.000 |
| | 0630- 2- 12 | CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE | LF | 2,453.000 |
| | 0630- 2- 14 | CONDUIT, FURNISH & INSTALL, ABOVEGROUND | LF | 240.000 |
| | 0632- 7- 1 | SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL | PI | 5.000 |
| | 0632- 7- 6 | SIGNAL CABLE, REMOVE- INTERSECTION | PI | 5.000 |
| | 0633- 1-410 | FIBER OPTIC CABLE, RELOCATE, OVERHEAD | LF | 600.000 |
| | 0633- 6- | FIBER OPTIC CABLE LOCATOR | DA | 400.000 |
| | 0634- 4-152 | SPAN WIRE ASSEMBLY, F&I, TWO POINT, DIAGONAL | PI | 3.000 |
| | 0634- 4-600 | SPAN WIRE ASSEMBLY, REMOVE- POLES REMAIN | PI | 3.000 |
| | 0635- 2- 11 | PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE | EA | 120.000 |
| | 0641- 2- 60 | PRESTRESSED CONCRETE POLE, COMPLETE POLE REMOVAL- PEDESTAL/SERVICE POLE | EA | 3.000 |
| | 0646- 1- 11 | ALUMINUM SIGNALS POLE, PEDESTAL | EA | 25.000 |
| | 0646- 1- 60 | ALUMINUM SIGNALS POLE, REMOVE | EA | 7.000 |
| | 0650- 1- 14 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 3 SECTION, 1 WAY | AS | 18.000 |
| | 0650- 1- 19 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL ALUMINUM, 5 SECTION CLUSTER, 1 WAY | AS | 4.000 |
| | 0650- 1- 24 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE W/ALUM TOP, 3 SECTION, 1 WAY | AS | 16.000 |
| | 0650- 1- 25 | VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE WITH ALUMINUM TOP SECTION, 3 SECTION, 2-4 WAYS | AS | 6.000 |
| | 0653- 1- 11 | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY | AS | 28.000 |
| | 0653- 1- 12 | PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 2 WAYS | AS | 2.000 |
| | 0653- 1- 60 | PEDESTRIAN SIGNAL, REMOVE PED SIGNAL- POLE/PEDESTAL TO REMAIN | AS | 13.000 |
| | 0660- 1-109 | LOOP DETECTOR INDUCTIVE, F&I, TYPE 9 | EA | 15.000 |
| | 0660- 1-110 | LOOP DETECTOR INDUCTIVE, F&I, TYPE 10 | EA | 7.000 |
| | 0660- 1-600 | LOOP DETECTOR INDUCTIVE, REMOVE- CABINET TO REMAIN | EA | 28.000 |
| | 0660- 2-106 | LOOP ASSEMBLY, F&I, TYPE F | AS | 34.000 |
| | 0660- 4- 11 | VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL CABINET EQUIPMENT | EA | 6.000 |
| | 0660- 4- 12 | VEHICLE DETECTION SYSTEM- VIDEO, FURNISH & INSTALL ABOVE GROUND EQUIPMENT | EA | 17.000 |
| | 0660- 4- 61 | VEHICLE DETECTION SYSTEM- VIDEO, REMOVE CABINET EQUIPMENT | EA | 4.000 |

Call Order: 003 Proposal: E51F3

| ALT | Item | Description | Unit | Quantity |
|-----|--------------|---|------|----------|
| | 0660- 4- 62 | VEHICLE DETECTION SYSTEM- VIDEO, REMOVE ABOVE GROUND EQUIPMENT | EA | 13.000 |
| | 0663- 1-122 | SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR | EA | 4.000 |
| | 0663- 1-123 | SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS | EA | 4.000 |
| | 0665- 1- 11 | PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD | EA | 30.000 |
| | 0665- 1- 60 | PEDESTRIAN DETECTOR, REMOVE- POLE/PEDESTAL TO REMAIN | EA | 10.000 |
| | 0671- 2- 11 | TRAFFIC CONTROLLER WITHOUT CABINET, F&I IN EXISTING CABINET, NEMA | EA | 2.000 |
| | 0671- 2- 40 | TRAFFIC CONTROLLER, MODIFY | EA | 3.000 |
| | 0671- 2- 60 | TRAFFIC CONTROLLER, REMOVE- CABINET TO REMAIN | EA | 2.000 |
| | 0676- 1-500 | TRAFFIC SIGNAL CONTROLLER CABINET, ADJUST/MODIFY | EA | 3.000 |
| | 0678- 1-104 | CONTROLLER ACCESSORIES, REPLACE EXISTING- FURNISH AND INSTALL, LOAD SWITCH | EA | 2.000 |
| | 0680- 1-600 | SYSTEM CONTROL EQUIPMENT, REMOVE COMPLETE SYSTEM | EA | 4.000 |
| | 0685- 2- 1 | REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL | EA | 4.000 |
| | 0695- 1- 1 | TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL | EA | 10.000 |
| | 0695- 6- 12 | TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS | EA | 10.000 |
| | 0695- 7-162 | TRAFFIC MONITORING SITE CABINET, F&I, TYPE 3, 2 PANE BACK, PEDESTAL MOUNT | EA | 2.000 |
| | 0695- 7-600 | TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET | EA | 2.000 |
| | 0700- 3-201 | SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF | EA | 4.000 |
| | 0700- 3-501 | SIGN PANEL, RELOCATE, UP TO 12 SF | EA | 1.000 |
| | 0700- 3-601 | SIGN PANEL, REMOVE, UP TO 12 SF | EA | 12.000 |
| | 0700- 5- 21 | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL OVERHEAD MOUNT, UP TO 12 SF | EA | 3.000 |
| | 0700- 5- 22 | INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF | EA | 9.000 |
| | 0700- 5- 60 | INTERNALLY ILLUMINATED SIGN, REMOVE | EA | 12.000 |
| | 0700-141-360 | ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, BLANK OUT SIGN <12 SF | EA | 1.000 |
| | 0700-141-903 | ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, REMOVE - OVERHEAD MOUNT | EA | 1.000 |
| | 0920-681-100 | CONNECTED VEHICLE ROAD SIDE UNIT | EA | 1.000 |