## Florida Department of Transportation Bid Solicitation Notice and Approximate Quantities

Letting: 05240206 Call Order: 006 Proposal: E55C9 District:05

Counties: ORANGE

Road Name: SR 50/ Misty Oaks Outfall

Limits: Midpoint

Project(s): 41232667236(\*) Federal Aid No: N/A

Total Roadway Length: 0.000 Miles Contract Days: 90

Total Bridge Length: 0.000 Miles Letting Date: 02/06/24

Total Proposal Length: 0.000 Miles Contract Execution Days: 10

Special Start Date: N/A
Aguis/Flexible Start Time: 14

Proposal Budget Estimate: \$160,000.00

Please read the full advertisement

Description: FDOT District 5

Proposal ID No.: E55C9

Financial Project No.: 412326-6-72-36

Fiscal Year: 2024 County: Orange

Contract Calendar Days: 90

Lead Time: 14 days

This is a Maintenance Pay Item Contract.

## Intent:

The work under this Contract consists of construction of an outfall from the retention pond located off SR 50 near the Misty Oaks Apartment Complex in Orange County, Florida.

## Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

Call Order: 006 Proposal: E55C9

| can order too Tropodan 2000                           |              |  |      |           |
|---|--------------|--|------|-----------|
| ALT   | Item         | Description  | Unit | Quantity  |
| Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF) |              |  |      |           |
|   | 0101- 1-     | MOBILIZATION   | LS   | 1.000     |
|   | 0102- 1-     | MAINTENANCE OF TRAFFIC                               | LS   | 1.000     |
|   | 0104- 10- 3  | SEDIMENT BARRIER                                     | LF   | 920.000   |
|   | 0110- 1- 1   | CLEARING & GRUBBING                                  | LS   | 1.000     |
|   | 0120- 1-     | REGULAR EXCAVATION                                   | CY   | 107.000   |
|   | 0120- 6-     | EMBANKMENT   | CY   | 109.000   |
|   | 0425- 2-91   | MANHOLES, J-8, <10'                                  | EA   | 2.000     |
|   | 0430-175-136 | PIPE CULVERT, OPT MATERIAL, ROUND, 36"S/CD           | LF   | 227.000   |
|   | 0430-984-138 | MITERED END SECTION , OPTIONAL ROUND, 36" SIDE DRAIN | EA   | 1.000     |
|   | 0524- 1- 1   | CONCRETE DITCH PAVT, NON REINFORCED, 3"              | SY   | 17.000    |
|   | 0530- 3- 4   | RIPRAP, RUBBLE, F&I, DITCH LINING                    | TN   | 70.000    |
|   | 0570- 1- 2   | PERFORMANCE TURF, SOD                                | SY   | 1,949.000 |