

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05240104 Call Order: 001 Proposal: E50F0 District:05
Counties: LAKE, SUMTER
Road Name: US 27 OVER US 192SR 471 OVER LITTLE WITHLACOOCHEE RIVER DECK
Limits: 11200000
Project(s): 44985615201(*) Federal Aid No: N/A
Total Roadway Length: 0.000 Miles Contract Days: 150
Total Bridge Length: 0.074 Miles Letting Date: 01/04/24
Total Proposal Length: 0.074 Miles Contract Execution Days: 10
Special Start Date: N/A
Aquis/Flexible Start Time: 30
Proposal Budget Estimate: \$704,185.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of bridge deck epoxy overlay, header repair, and joint rehabilitation of SR 25 (US 27) over US 192 (Bridge Nos. 110036 & 110940) in Lake County and SR 471 over the Little Withlacoochee River (Bridge No. 180012) in Sumter County.

Marine General Liability Insurance required.

PREQUALIFICATION REQUIRED

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 001 Proposal: E50F0

ALT	Item	Description	Unit	Quantity
Section 0001 Structures				
	0403- 1-100	EPOXY CONCRETE OVERLAY FOR CONCRETE BRIDGE DECKS	SY	3,628.000
	0403- 2-100	RESTORE SPALLED AREAS FOR CONCRETE BRIDGE DECKS	CF	10.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	456.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	675.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	63.700
Section 0002 Roadway				
	0101- 1-	MOBILIZATION (44985615201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44985615201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	930.000
	0102- 60-	WORK ZONE SIGN	ED	1,750.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	170.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	221.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	170.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	170.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	40.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44985615201)	LS	1.000
Section 0003 Signing				
	0701- 17-101	PROFILED THERMOPLASTIC, STANDARD- CONCRETE SURFACES, WHITE, SOLID, 6"	GM	0.080
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	50.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44985615201)	LS	1.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.136
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6", 10-30 SKIP OR 3-9 LANE DROP	GM	0.136
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.148