Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: 05240104 Call Order: 004 Proposal: E56C8 District:05
Counties: VOLUSIA

Road Name: Nova Canal Cleaning
Limits: Midpoint

Project(s): 41232657248(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	180
Total Bridge Length:	0.000 Miles	Letting Date:	01/04/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: $1,206,899.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID: E56C8
Project No: 412326-5-72-48
Fiscal Year: 2024
Counties: Volusia
Contract Calendar Days: 180
Lead Time: 14 days

This is a Maintenance Pay Item Project.

INTENT AND SCOPE:
The work under this Contract consists of the restoration of the design bottom width and depth of the Nova Canal drainage system; work includes cleaning, reshaping, clearing & grubbing, tree and vegetation removal, herbicide application and turf restoration in a series of canal segments between Canal View Boulevard and 10th Street in Volusia County.

Call Order: 004 Proposal: E56C8

ALT	Item	Description	Unit	Quantity
Section 0001 OUTFALL DITCHES, CLEAN AND REPAIR (LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0120- 6-	EMBANKMENT	CY	6,940.000
	0120- 10- 23	CLEAN AND RESHAPE DITCH, HAUL, DITCH WIDTH GREATER THAN 30'	LF	24,285.000
	E110- 2-	CLEARING & GRUBBING	AC	4.300
	E111- 2- 3	DITCH AND CANAL, CLEAN, GRADE AND RESHAPE, GREATER THAN 30' WIDE	LF	24,285.000
	E573- 1-	HYDRO-SEEDING - APPLICATION OF SLURRY INCLUDING WOOD FIBER, SEED, FERTILIZER, TACKIFIER & DYE	SY	8,329.000
	E580-337- 4	HERBICIDE (STRIP APPLICATION)(AQUATIC)	AC	17.210