

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting:	05240305	Call Order: 006	Proposal: E56C5	District:05
Counties:	VOLUSIA			
Road Name:	Asphalt Repair			
Limits:	Midpoint			
Project(s):	42914217218(*)	Federal Aid No: N/A		
Total Roadway Length:	0.000 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	03/05/24	
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	14	

Proposal Budget Estimate: \$900,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID.: E56C5
Financial Project No.: 429142-1-72-18
Fiscal Year: 2024
County: Volusia
Calendar Days: 120
Lead Time: 14 days

This is a Maintenance Pay Item Contract.

Intent:

The work under this Contract consists of milling and resurfacing sections of asphalt pavement on SR 421 (Dunlawton Avenue) from SR-9 to SR-5A in Volusia County. Work includes the restoration of pavement markings.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Asphalt Paving projects, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Hot Plant Mix Bituminous Course" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 006 Proposal: E56C5

ALT	Item	Description	Unit	Quantity
Section 0001 ASPHALT REPAIR (MECHANICAL) (TN)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	28.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	28.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	29,684.000
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	2,448.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	125.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	5.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	9.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	9.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	9.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	570.000
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	1,400.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	1,400.000
	E711- 11-121	THERMOPLASTIC, STANDARD, WHITE, SOLID, 6"	LF	6,564.000
	E711- 11-141	THERMOPLASTIC, STANDARD, WHITE, SKIP, 6"	LF	31,000.000
	E711- 11-221	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 6"	LF	6,514.000