

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05240305 Call Order: 008 Proposal: E58C6 District:05
Counties: ORANGE

Road Name: Baylarian Outfall Repair
Limits: Midpoint

Project(s): 41232657249(*)

Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	60
Total Bridge Length:	0.000 Miles	Letting Date:	03/05/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$165,000.00

Please read the full advertisement

Description:

FDOT District 5
Proposal ID No.: E58C6
Financial Project No.: 412326-5-72-49
Fiscal Year: 2024
County: Orange
Calendar Days: 60
Lead Time: 14 days

This is a Maintenance Pay Item Contract.

Intent:

The work under this Contract consists of the installation of a modified Type J-8 junction box, pipe installation, and minor roadway restoration, located within a Department owned drainage easement on Baylarian Blvd, Orlando.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Drainage Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Drainage" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 008 Proposal: E58C6

ALT	Item	Description	Unit	Quantity
Section 0001 REPAIR/REPLACE STRM-SIDE-CROSS DRAIN(LF)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0104- 10- 3	SEDIMENT BARRIER	LF	58.000
	0104- 11-	FLOATING TURBIDITY BARRIER	LF	38.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	2.000
	0110- 1- 1	CLEARING & GRUBBING	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	10.000
	0110- 23-	TREE REMOVAL	EA	1.000
	0160- 4-	TYPE B STABILIZATION	SY	72.000
	0285-704-	OPTIONAL BASE, BASE GROUP 04	SY	72.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	79.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	21.040
	0425- 2- 92	MANHOLES, J-8, >10'	EA	1.000
	0430-175-148	PIPE CULVERT, OPT MATERIAL, ROUND, 48"S/CD	LF	10.000
	0520- 2- 4	CONCRETE CURB, TYPE D	LF	39.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	8.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	26.000
	0580- 5- 25	LANDSCAPE- TREES, DISTRICT SPECIFIED FROM PROJECT LIST, CONTAINER GROWN 65 GALLON	EA	1.000