

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05240507 Call Order: 015 Proposal: E59C9 District:05
Counties: ORANGE

Road Name: Concrete Roadway Repair
Limits: Midpoint

Project(s): 42795617264(*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	90
Total Bridge Length:	0.000 Miles	Letting Date:	05/07/24
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	14

Proposal Budget Estimate: \$380,000.00

Please read the full advertisement

Description:

FDOT District 5
Contract Number: E59C9
Financial Project No. 427956-1-72-64
Fiscal Year: 2024
County: Orange
Calendar Days: 90
Lead Time: 14 Days

This is a Maintenance Pay Item Contract.

Intent:

The work under this Contract consists of concrete roadway slab & traffic separator repair; includes pavement markings and RPMs, manhole cover adjustment, sign and delineator replacement in various locations on SR 15/600 (US 17-92) in Orange County.

Experience:

For this Contract the Contractor is required to have at least three (3) years of experience in the performance of Concrete Pavement Repair, or the Project Superintendent must have at least three (3) years of like experience as a Superintendent. A Contractor that presently has a certificate of prequalification with the Department in "Portland Cement Concrete Roadway Paving" will suffice to meet the above requirements.

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Call Order: 015 Proposal: E59C9

ALT	Item	Description	Unit	Quantity
Section 0001 CONCRETE REPAIR (CY)				
	0101- 1-	MOBILIZATION	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	500.530
	0353- 70-	CONCRETE PAVEMENT SLAB REPLACEMENT	CY	238.680
	0425- 7-	MANHOLE COVER- REPLACE	EA	1.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	462.000
	0700- 1- 40	SINGLE POST SIGN, INSTALL	AS	4.000
	0700- 1- 60	SINGLE POST SIGN, REMOVE	AS	4.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	7.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	13.000
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	160.000
	0711- 14-141	THERMOPLASTIC, PREFORMED, WHITE, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.010
	0711- 14-341	THERMOPLASTIC, PREFORMED, BLACK, 2-4 DOTTED GUIDELINE ON CONCRETE SURFACES	GM	0.010
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	4.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.047
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.119
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	150.000