

**Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities**

Letting: 05250401 Call Order: 001 Proposal: E53F1 District:05

Counties: BREVARD

Road Name: SR 404

Limits: 70004000

Project(s): 44878515201(*) Federal Aid No: N/A

Total Roadway Length: 3.118 Miles Contract Days: 210

Total Bridge Length: 0.891 Miles Letting Date: 04/01/25

Total Proposal Length: 4.009 Miles Contract Execution Days: 10

Special Start Date: N/A

Aquis/Flexible Start Time: 120 LEAD

Proposal Budget Estimate: \$11,592,584.00

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing on SR 404 from west of SR 5 (US 1) (MP 0.581) to SR A1A (MP 4.590) approximately 4.009 miles in Brevard County. Additional items include milling and resurfacing of the interchange ramps at SR 5, CR-3 and SR 513, paved shoulder construction, signalization and installation of wrong way driving vehicle detection systems.

PREQUALIFICATION REQUIRED

Call Order: 001 Proposal: E53F1

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44878515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44878515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	104.000
	0102- 25-100	PEDESTRIAN ESCORT OPERATION	HR	80.000
	0102- 60-	WORK ZONE SIGN	ED	10,800.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,260.000
	0102- 74- 8	CHANNELIZING DEVICE- PEDESTRIAN LCD (LONGITUDINAL CHANNELIZING DEVICE)	FD	8,125.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	420.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	2,550.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	210.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	210.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	210.000
	0102-115-	TYPE III BARRICADE	ED	720.000
	0104- 10- 3	SEDIMENT BARRIER	LF	5,087.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	117.000
	0107- 1-	LITTER REMOVAL	AC	744.150
	0107- 2-	MOWING	AC	630.740
	0110- 1- 1	CLEARING & GRUBBING (44878515201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	353.000
	0120- 1-	REGULAR EXCAVATION	CY	403.100

Call Order: 001 Proposal: E53F1

ALT	Item	Description	Unit	Quantity
	0120- 6-	EMBANKMENT	CY	493.100
	0160- 4-	TYPE B STABILIZATION	SY	4,559.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	1,806.000
	0285-710-	OPTIONAL BASE, BASE GROUP 10	SY	237.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	648.000
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	63,630.000
	0327- 70- 5	MILLING EXISTING ASPHALT PAVEMENT, 2" AVG DEPTH	SY	23,227.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	3,521.000
	0327- 70- 13	MILLING EXISTING ASPHALT PAVEMENT, 1 3/4" AVG DEPTH	SY	1,943.000
	0327- 70- 15	MILLING EXISTING ASPHALT PAVEMENT, 2 3/4" AVG DEPTH	SY	66,820.000
	0334- 1- 13	SUPERPAVE ASPHALTIC CONC, TRAFFIC C	TN	192.100
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	15,299.200
	0337- 7- 25	ASPHALT CONCRETE FRICTION COURSE, INC BIT, FC-5, PG 76-22	TN	2,747.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC C, FC-12.5, PG 76-22	TN	5,708.300
	0339- 1-	MISCELLANEOUS ASPHALT PAVEMENT	TN	20.900
	0425- 1-201	INLETS, CURB, TYPE 9, <10'	EA	2.000
	0425- 1-910	INLETS, CLOSED FLUME	EA	2.000
	0430-175-118	PIPE CULVERT,OPTIONAL MATERIAL,ROUND, 18"S/CD	LF	14.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	120.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	312.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	305.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	39.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	15.000
	0527- 2-	DETECTABLE WARNINGS	SF	24.000
	0536- 1- 1	GUARDRAIL -ROADWAY, GENERAL TL-3	LF	608.000
	0536- 8-122	GUARDRAIL TRANSITION CONNECTION TO RIGID BARRIER, F&I-INDEX 536-002, APPROACH TL-3	EA	1.000
	0536- 73-	GUARDRAIL REMOVAL	LF	607.000
	0536- 85- 20	GUARDRAIL END TREATMENT- TRAILING ANCHORAGE	EA	1.000
	0536- 85- 24	GUARDRAIL END TREATMENT- PARALLEL APPROACH TERMINAL	EA	1.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	15,535.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	75.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	184.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	9.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	12.000
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	12.000
	0695- 7-132	TRAFFIC MONITORING SITE CABINET, FURNISH & INSTALL, TYPE 3, PEDESTAL MOUNT	EA	3.000
	0695- 7-600	TRAFFIC MONITORING SITE CABINET, REMOVE EXISTING CABINET	EA	3.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	8.746
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	1.007
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	150.000

Call Order: 001 Proposal: E53F1

ALT	Item	Description	Unit	Quantity
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	836.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	359.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	6.789
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.767
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	15.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	52.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	102.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	8.348
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.081
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44878515201)	LS	1.000
Section 0002 Signing				
	0546- 72- 1	GROUND-IN RUMBLE STRIPS, 16"	GM	7.118
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	82.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	32.000
	0700- 1-113	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	9.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	110.000
	0700- 2-113	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 20.1-30.0 SF	EA	3.000
	0700- 2-114	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 30.1-50.0 SF	EA	2.000
	0700- 2-115	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 50.1-100.0 SF	EA	1.000
	0700- 2-116	MULTI-COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 100.1-200.0 SF	EA	7.000
	0700- 2-600	MULTI-COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	7.000
	0700- 3-101	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, UP TO 12 SF	EA	1.000
	0700- 3-102	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 12-20 SF	EA	2.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-602	SIGN PANEL, REMOVE, 12-20 SF	EA	2.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	7.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	209.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	2,648.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	4.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44878515201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	836.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	219.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.767

Call Order: 001 Proposal: E53F1

ALT	Item	Description	Unit	Quantity
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	10.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	51.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	102.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.081
	0711- 14-123	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 12" FOR CROSSWALK	LF	150.000
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	140.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	7.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	7.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	5.480
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.786
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	4.454
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	5.580
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.260
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.293
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.279
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.768
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.740
	0713-103-181	PERMANENT TAPE, WHITE, 10-30 SKIP, 6" WIDE, FOR CONCRETE SURFACES	GM	1.672
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	1.740
	0713-107-	PREFORMED/PERMANENT TAPE, REMOVE	SF	10,338.000
	0714- 10-	GREEN-COLORED PAVEMENT MARKINGS, BIKE LANE	SF	6,048.000
Section 0003 Signalization				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	1,214.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	336.000
	0632- 7- 1	SIGNAL CABLE- NEW OR RECONSTRUCTED INTERSECTION, FURNISH & INSTALL	PI	1.000
	0632- 7- 6	SIGNAL CABLE, REMOVE- INTERSECTION	PI	1.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	23.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	1.000
	0639- 1-620	ELECTRICAL POWER SERVICE, REMOVE UNDERGROUND	AS	1.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	26.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	1.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	1.000
	0646- 1- 11	ALUMINUM SIGNALS POLE, PEDESTAL	EA	1.000
	0646- 1- 60	ALUMINUM SIGNALS POLE, REMOVE	EA	1.000
	0649- 21- 6	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 50'	EA	1.000

Call Order: 001 Proposal: E53F1

ALT	Item	Description	Unit	Quantity
	0649- 21- 10	STEEL MAST ARM ASSEMBLY, FURNISH AND INSTALL, SINGLE ARM 60'	EA	1.000
	0649- 26- 5	STEEL MAST ARM ASSEMBLY, REMOVE, DEEP FOUNDATION- BOLT ON ATTACHMENT	EA	1.000
	0650- 1- 34	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 3 SECTION, 1 WAY	AS	4.000
	0650- 1- 39	VEHICULAR TRAFFIC SIGNAL, FURNISH & INSTALL POLYCARBONATE, 5 SECTION CLUSTER, 1 WAY	AS	1.000
	0650- 2-102	VEHICULAR SIGNAL AUXILIARIES, REPAIR/REPLACE/RETROFIT- FURNISH & INSTALL, BACKPLATE- BLACK WITH REFLECT BORDER	EA	3.000
	0653- 1- 11	PEDESTRIAN SIGNAL, FURNISH & INSTALL LED COUNTDOWN, 1 WAY	AS	1.000
	0660- 1-109	LOOP DETECTOR INDUCTIVE, F&I, TYPE 9	EA	9.000
	0660- 1-110	LOOP DETECTOR INDUCTIVE, F&I, TYPE 10	EA	1.000
	0660- 2-101	LOOP ASSEMBLY- F&I, TYPE A	AS	2.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	9.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	9.000
	0663- 1-122	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, DETECTOR	EA	1.000
	0663- 1-123	SIGNAL PRIORITY AND PREEMPTION SYSTEM, FURNISH AND INSTALL, GPS, CABINET ELECTRONICS	EA	1.000
	0665- 1- 11	PEDESTRIAN DETECTOR, FURNISH & INSTALL, STANDARD	EA	1.000
	0670- 5-111	TRAFFIC CONTROLLER ASSEMBLY, F&I, NEMA, 1 PREEMPTION	AS	1.000
	0670- 5-600	TRAFFIC CONTROLLER ASSEMBLY, REMOVE CONTROLLER WITH CABINET	AS	1.000
	0682- 1-113	ITS CCTV CAMERA, F&I, DOME PTZ ENCLOSURE - PRESSURIZED, IP, HIGH DEFINITION	EA	1.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	1.000
	0685- 1- 13	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE WITH CABINET	EA	1.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	1.000
	0700- 5- 22	INTERNALLY ILLUMINATED SIGN, FURNISH & INSTALL, OVERHEAD MOUNT, 12-18 SF	EA	3.000
	0700-141-360	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I OVERHEAD MOUNT, BLANK OUT SIGN <12 SF	EA	1.000
Section 0004 Intelligent Transportation System				
	0110- 2- 2	SELECTIVE CLEARING AND GRUBBING, AREAS WITH TREES TO REMAIN	AC	0.010
	0611- 1- 1	ITSFM SUBSURFACE DOCUMENTATION- PROJECT LENGTH	MI	4.016
	0611- 2- 1	ITSFM LOCATION DOCUMENTATION- INTERSECTION	EA	1.000
	0611- 2- 2	ITSFM LOCATION DOCUMENTATION- ITS SITE	EA	4.000
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	17,269.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	3,855.000
	0630- 2- 14	CONDUIT, FURNISH & INSTALL, ABOVEGROUND	LF	20.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	4,551.000
	0633- 1-121	FIBER OPTIC CABLE, F&I, UNDERGROUND,2-12 FIBERS	LF	4,454.000
	0633- 1-124	FIBER OPTIC CABLE, F&I, UNDERGROUND, 97 - 144 FIBERS	LF	25,142.000
	0633- 2- 31	FIBER OPTIC CONNECTION, INSTALL, SPLICE	EA	184.000

Call Order: 001 Proposal: E53F1

ALT	Item	Description	Unit	Quantity
	0633- 2- 32	FIBER OPTIC CONNECTION, INSTALL, TERMINATION	EA	60.000
	0633- 3- 11	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE ENCLOSURE	EA	5.000
	0633- 3- 12	FIBER OPTIC CONNECTION HARDWARE, F&I, SPLICE TRAY	EA	17.000
	0633- 3- 14	FIBER OPTIC CONNECTION HARDWARE, F&I, BUFFER TUBE FAN OUT KIT	EA	5.000
	0633- 3- 16	FIBER OPTIC CONNECTION HARDWARE, F&I, PATCH PANEL- FIELD TERMINATED	EA	5.000
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	210.000
	0633- 8- 11	MULTI-CONDUCTOR COMMUNICATION CABLE, FURNISH & INSTALL, CAT 6	LF	128.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	35.000
	0635- 2- 12	PULL & SPLICE BOX, F&I, 24" X 36" COVER SIZE	EA	43.000
	0635- 2- 13	PULL & SPLICE BOX, F&I, 30" X 60" RECTANGULAR OR 36" ROUND COVER SIZE	EA	6.000
	0635- 3- 12	JUNCTION BOX, FURNISH & INSTALL, MOUNTED	EA	24.000
	0639- 1-112	ELECTRICAL POWER SERVICE, F&I, OVERHEAD METER PURCHASED BY CONTRACTOR FROM POWER COMPANY	AS	1.000
	0639- 1-122	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER PURCHASED BY CONTRACTOR	AS	2.000
	0639- 2- 1	ELECTRICAL SERVICE WIRE, FURNISH & INSTALL	LF	4,247.000
	0639- 3- 11	ELECTRICAL SERVICE DISCONNECT, F&I, POLE MOUNT	EA	7.000
	0639- 6-111	ELECTRICAL POWER SERVICE- TRANSFORMER, F&I, <5 KVA, SINGLE PHASE, COPPER WINDINGS	EA	3.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	7.000
	0660- 7- 21	VEHICLE DETECTION SYSTEM- WRONG WAY FOR EXIT RAMP, 1 OR 2 LANES, AC POWERED	EA	8.000
	0676- 2-122	ITS CABINET, FURNISH & INSTALL, POLE MOUNT WITH SUNSHIELD, 336S, 24" W X 46" H X 22" D	EA	4.000
	0684- 1- 1	MANAGED FIELD ETHERNET SWITCH, FURNISH & INSTALL	EA	4.000
	0684- 5- 1	MEDIA CONVERTER, FURNISH & INSTALL	EA	8.000
	0685- 1- 11	UNINTERRUPTIBLE POWER SUPPLY, FURNISH AND INSTALL, LINE INTERACTIVE	EA	4.000
	0685- 2- 1	REMOTE POWER MANAGEMENT UNIT- RPMU, FURNISH AND INSTALL	EA	4.000
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	14.000
	0700- 13- 12	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 2'	EA	14.000
	0700-141-140	ENHANCED HIGHWAY SIGN ASSEMBLY, AC POWERED, F&I GROUND MOUNT, HIGHLIGHTED SIGN <12 SF	EA	14.000