

**Florida Department of Transportation  
Bid Solicitation Notice and Approximate Quantities**

Letting: 05250401 Call Order: 002 Proposal: E54F9 District:05  
 Counties: BREVARD, DIST/ST-WIDE, FLAGLER, LAKE, MARION, ORANGE, OSCEOLA, SEMINOLE, SUMTER, VOLUSIA

Road Name: Traffic Ops Roadway Pushbutton Contract with Mobilization  
 Limits: Midpoint

Project(s): 44081655203(\*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	730
Total Bridge Length:	0.000 Miles	Letting Date:	04/01/25
Total Proposal Length:	0.000 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	

Proposal Budget Estimate: \$1,000,000.00

Please read the full advertisement

**Description:**

The improvements under this Contract may consist of constructing new or resurfacing travel lanes, miscellaneous concrete work, such as median islands and sidewalks, along with sodding and pavement marking.

The intent of this contract is to provide means for the DEPARTMENT to quickly respond to unexpected safety and/or operational issues for a period of two (2) years or until the contracted amount has been reached.

The Contractor shall furnish all labor, materials, equipment, tools, transportation, and supplies required to complete the work in accordance with the work plan, specifications, procedures, and terms of the contract. The DEPARTMENT will not specify contractor crew size, work methods or equipment complements, provided the desired work quality is achieved as evaluated by the Project Engineer. The work under this Contract will be controlled by the issuance of Work Documents. All work in this contract is considered specialty work. The number of work documents for the contract will be limited by a budgetary cap of \$1,000,000.

The quantities shown on the Bid Price Proposal are approximate and only represent estimated planned requirements based on historical or specific project needs. The Department does not guarantee any maximum or minimum quantity, any range of quantities, or the exact quantities shown for each bid item. The Departments estimated quantities and the Contractors bid price will be used to calculate a total bid amount. This total bid amount will then be used to determine the low bidder; however, actual payment under the awarded contract will be based on actual quantities completed. For this Contract in which specific sites are not identified at the time of letting, the Engineer will issue a Work Document. Work Documents will identify the location, description, amount of work to be accomplished, and the number of calendar days to complete the work.

**PREQUALIFICATION REQUIRED**

**Call Order: 002 Proposal: E54F9**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Roadway</b>				
	0101- 1- 1	MOBILIZATION- FOR WORK ORDER/PUSH BUTTON CONTRACTS (DO NOT BID) (44081645202)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,750.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	10,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	252.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	418.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	60.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	60.000
	0102-909-	TEMPORARY RAISED RUMBLE STRIPS- PER DAY, INCLUDES ALL SETS AND RELOCATIONS	DA	50.000
	0104- 10- 3	SEDIMENT BARRIER	LF	400.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	12.000

**Call Order: 002 Proposal: E54F9**

ALT	Item	Description	Unit	Quantity
	0110- 2- 1	CLEARING & GRUBBING (PUSH BUTTON CONTRACT)	AC	0.400
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	619.000
	0120- 1-	REGULAR EXCAVATION	CY	257.900
	0120- 2- 2	BORROW EXCAVATION, TRUCK MEASURE	CY	50.000
	0160- 4-	TYPE B STABILIZATION	SY	897.000
	0285-701-	OPTIONAL BASE, BASE GROUP 01	SY	260.000
	0285-709-	OPTIONAL BASE, BASE GROUP 09	SY	455.000
	0285-715-	OPTIONAL BASE, BASE GROUP 15	SY	450.000
	0327- 70- 1	MILLING EXISTING ASPHALT PAVEMENT, 1" AVG DEPTH	SY	190.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	1,133.000
	0327- 70- 19	MILLING EXISTING ASPHALT PAVEMENT, 3/4" AVG DEPTH	SY	1,800.000
	0334- 1- 52	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC B, PG76-22	TN	36.400
	0337- 7- 81	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC B, FC-12.5, PG 76-22	TN	60.100
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	90.000
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	300.000
	0520- 1- 10	CONCRETE CURB & GUTTER, TYPE F	LF	34.000
	0520- 2- 2	CONCRETE CURB, TYPE B	LF	300.000
	0520- 5- 11	TRAFFIC SEPARATOR CONCRETE-TYPE I, 4' WIDE	LF	215.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	2,092.000
	0522- 1-	CONCRETE SIDEWALK AND DRIVEWAYS, 4" THICK	SY	14.000
	0522- 2-	CONCRETE SIDEWALK AND DRIVEWAYS, 6" THICK	SY	69.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	780.000
<b>Section 0002 Signing</b>				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	6.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	6.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	5.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	3.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	6.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	521.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.133
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.058
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	52.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	24.000
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	1.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	4.000
	0710- 11-180	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, YIELD LINE	LF	15.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.086
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	146.000

**Call Order: 002 Proposal: E54F9**

ALT	Item	Description	Unit	Quantity
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.019
	0710- 11-290	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, ISLAND NOSE	SF	456.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.006
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	80.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	24.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.030
	0711- 11-160	THERMOPLASTIC, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	9.000
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	12.000
	0711- 11-180	THERMOPLASTIC, STANDARD, WHITE, YIELD LINE	LF	15.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.019
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.395
	0711- 15-102	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SOLID, 8"	GM	0.030
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.242
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.186
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.095
	0711- 16-171	THERMOPLASTIC, STANDARD OTHER SURFACES, WHITE, 6", 6-10 DOTTED MANAGED LANE MARKING	GM	0.019
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.057
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	854.000