

**Florida Department of Transportation**  
**Bid Solicitation Notice and Approximate Quantities**

Letting: 05250805 Call Order: 003 Proposal: E55F9 District:05

Counties: DIST/ST-WIDE/SEMINOLE, VOLUSIA

Road Name: SR 400 (I-4) Various Bridge Deck Repairs

Limits: 77160000

Project(s): 45370915201(\*) Federal Aid No: N/A

Total Roadway Length:	0.000 Miles	Contract Days:	130
Total Bridge Length:	0.141 Miles	Letting Date:	08/05/25
Total Proposal Length:	0.141 Miles	Contract Execution Days:	10
		Special Start Date:	N/A
		Aquis/Flexible Start Time:	30

Proposal Budget Estimate: \$548,244.00

Please read the full advertisement

**Description:**

The Improvements under this Contract consist of expansion joint replacement, milling & resurfacing approach slabs, and approach header replacement for Bridge Nos. 770086 & 770087 carrying SR 400 (I-4) over Orange Blvd & CFRC Railroad from MP 13.839 to MP 13.886, approximately 0.047 miles in Seminole County (77160); expansion joint replacement and joint header repairs for Bridge Nos. 790042 and 790100 carrying SR 400 (I-4) over Dirksen Drive from MP 3.496 to MP 3.563, approximately 0.067 miles in Volusia County (79110); and approach slab cleaning and sealing for Bridge Nos. 790166 & 790167 carrying Saxon Blvd over SR 400 (I-4) from MP 6.346 to MP 6.373, approximately 0.027 miles in Volusia County (79110).

**PREQUALIFICATION REQUIRED**

**Call Order: 003 Proposal: E55F9**

ALT	Item	Description	Unit	Quantity
<b>Section 0001 Structures</b>				
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (45370915201)	LS	1.000
	0110- 3-	REMOVAL OF EXISTING STRUCTURES/BRIDGES (45370915201)	LS	1.000
	0401- 70- 4	RESTORE SPALLED AREAS, PORTLAND CEMENT GROUT	CF	3.600
	0413-151-	METHACRYLATE MONOMER	GA	40.000
	0413-154-	CLEANING & SEALING CONCRETE SURFACES - PENETRANT SEALER OR METHACRYLATES	SF	3,962.000
	0415- 1- 9	REINFORCING STEEL- APPROACH SLABS	LB	522.000
	0458- 1- 21	BRIDGE DECK EXPANSION JOINT, REHABILITATION, POURED JOINT WITH BACKER ROD	LF	1,048.000
	0458- 2-	POLYMER NOSING FOR BRIDGE DECK EXPANSION JOINT	CF	59.200
<b>Section 0002 Roadway</b>				
	0101- 1-	MOBILIZATION (45370915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45370915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	920.000
	0102- 60-	WORK ZONE SIGN	ED	1,840.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,367.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	247.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	216.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	194.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	194.000
	0102-913- 21	REMOVABLE TAPE, WHITE, SOLID 6"	GM	0.027
	0102-913- 22	REMOVABLE TAPE, WHITE, 10'-30', 3'-9', 6'-10', or 2'-4' SKIP, 6" WIDE	GM	0.019

**Call Order: 003 Proposal: E55F9**

ALT	Item	Description	Unit	Quantity
	0102-913- 29	REMOVABLE TAPE, WHITE, MESSAGE, SYMBOL OR ARROW	EA	1.000
	0102-913- 31	REMOVABLE TAPE, YELLOW, SOLID, 6"	GM	0.015
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	388.000
	0334- 1- 55	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC E, PG76-22	TN	21.200
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE,TRAFFIC E, FC-12.5, PG 76-22	TN	32.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	12.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	0.022
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	0.044
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	0.022
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45370915201)	LS	1.000
<b>Section 0003 Signing</b>				
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	12.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45370915201)	LS	1.000
	0711- 14-570	THERMOPLASTIC, PREFORMED, WHITE WITH BLACK CONTRAST, ARROW ON CONCRETE SURFACE	EA	1.000
	0711- 15-101	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES WHITE, SOLID, 6"	GM	0.011
	0711- 15-131	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	0.022
	0711- 15-201	THERMOPLASTIC, STANDARD-OPEN GRADED ASPHALT SURFACES, YELLOW, SOLID, 6"	GM	0.011
	0713-103-101	PERMANENT TAPE, WHITE, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.027
	0713-103-141	PERMANENT TAPE, WHITE, 6-10 SKIP/DOTTED, 6" FOR CONCRETE SURFACES	GM	0.019
	0713-103-201	PERMANENT TAPE, YELLOW, SOLID, 6" FOR CONCRETE BRIDGES	GM	0.015