

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05250805	Call Order: 006	Proposal: E58F4	District:05
Counties:	OSCEOLA			
Road Name:	SR 60			
Limits:	92070000			
Project(s):	45062315201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.519 Miles	Contract Days:	120	
Total Bridge Length:	0.000 Miles	Letting Date:	08/05/25	
Total Proposal Length:	1.519 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:	\$1,916,018.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of Milling & Resurfacing, Shoulder Treatment, and Signing/Pavement Markings on State Road 60 from Turnpike (MP 20.261) to Indian River County Line (MP 21.820) approximately 1.519 miles in Osceola County.

PREQUALIFICATION REQUIRED

Call Order: 006 Proposal: E58F4

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45062315201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45062315201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	1,080.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	11,400.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 78- 1	TEMPORARY RAISED/RETROREFLECTIVE PAVEMENT MARKER, TYPE D	EA	956.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	240.000
	0104- 10- 3	SEDIMENT BARRIER	LF	891.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	23.000
	0107- 1-	LITTER REMOVAL	AC	137.990
	0107- 2-	MOWING	AC	137.990
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	62,475.000
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	5,154.200
	0570- 1- 3	PERFORMANCE TURF, SOD AND SOIL- SHOULDER TREATMENT INDEX 570-010	SY	7,907.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	3.409
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.041
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	77.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	3.049
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.152

Call Order: 006 Proposal: E58F4

ALT	Item	Description	Unit	Quantity
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	30.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	2.844
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.181
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45062315201)	LS	1.000
Section 0002 Signing				
	0546- 72- 3	GROUND-IN RUMBLE STRIPS, 8" SINUSOIDAL	GM	4.798
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	23.000
	0700- 1-112	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, 12.0-20.0 SF	EA	7.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	19.000
	0700- 3-103	SIGN PANEL, FURNISH & INSTALL GROUND MOUNT, 21-30 SF	EA	1.000
	0700- 3-601	SIGN PANEL, REMOVE, UP TO 12 SF	EA	1.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	956.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (45062315201)	LS	1.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	77.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.152
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	30.000
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.181
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	3.409
	0711- 16-102	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 8"	GM	0.041
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	3.049
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	2.844
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	3.000