

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05250805	Call Order: 007	Proposal: E59F3	District:05
Counties:	SEMINOLE			
Road Name:	SR 434			
Limits:	77120000			
Project(s):	44101515201(*)	Federal Aid No:	N/A	
Total Roadway Length:	1.787 Miles	Contract Days:	150	
Total Bridge Length:	0.000 Miles	Letting Date:	08/05/25	
Total Proposal Length:	1.787 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 DAYS FLEX	
Proposal Budget Estimate:	\$3,433,367.00			

Please read the full advertisement

Description:

The Improvements under this Contract consist of milling and resurfacing, sidewalk (detectible warnings), signing and pavement markings, and signals (loop replacements) on State Road 434 from Rangeline Road to US 17-92, approximately 1.787 miles in Seminole County.

PREQUALIFICATION REQUIRED

Call Order: 007 Proposal: E59F3

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (44101515201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (44101515201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	160.000
	0102- 60-	WORK ZONE SIGN	ED	12,733.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	12,960.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	481.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	298.000
	0102-104-	TEMPORARY SIGNALIZATION AND MAINTENANCE, INTERSECTION	ED	750.000
	0102-107- 1	TEMPORARY TRAFFIC DETECTION AND MAINTENANCE, INTERSECTION	ED	750.000
	0104- 18-	INLET PROTECTION SYSTEM	EA	79.000
	0107- 1-	LITTER REMOVAL	AC	43.300
	0107- 2-	MOWING	AC	43.300
	0327- 70- 4	MILLING EXISTING ASPHALT PAVEMENT, 3" AVG DEPTH	SY	58,129.000
	0327- 70- 6	MILLING EXISTING ASPHALT PAVEMENT, 1 1/2" AVG DEPTH	SY	13,714.000
	0327- 70- 7	MILLING EXISTING ASPHALT PAVEMENT, 4" AVG DEPTH	SY	624.000
	0334- 1- 53	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C, PG76-22	TN	4,881.400
	0337- 7- 83	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC C, FC-12.5, PG 76-22	TN	5,857.600
	0425- 5- 1	MANHOLE, ADJUST, UTILITIES	EA	30.000
	0527- 2-	DETECTABLE WARNINGS	SF	530.000
	0695- 1- 1	TRAFFIC MONITORING SITE VEHICLE SENSOR-NON-WEIGHT, FURNISH & INSTALL	EA	4.000

Call Order: 007 Proposal: E59F3

ALT	Item	Description	Unit	Quantity
	0695- 6- 12	TRAFFIC MONITORING SITE INDUCTIVE LOOP ASSEMBLY, FURNISH & INSTALL, 2 LOOPS	EA	4.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,196.000
	0710- 11-101	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID, 6"	GM	7.861
	0710- 11-102	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR INTERCHANGE AND URBAN ISLAND, 8"	GM	0.076
	0710- 11-123	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR CROSSWALK AND ROUNDABOUT, 12"	LF	5,099.000
	0710- 11-124	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	206.000
	0710- 11-125	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SOLID FOR STOP LINE OR CROSSWALK, 24"	LF	3,869.000
	0710- 11-131	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, SKIP, 10-30 OR 3-9 SKIP, 6" WIDE	GM	5.956
	0710- 11-141	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 DOTTED EXTENSION, 6"	GM	0.809
	0710- 11-160	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, MESSAGE OR SYMBOL	EA	22.000
	0710- 11-170	PAINTED PAVEMENT MARKINGS, STANDARD, WHITE, ARROWS	EA	113.000
	0710- 11-201	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID, 6"	GM	5.725
	0710- 11-224	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SOLID FOR DIAGONAL OR CHEVRON, 18"	LF	304.000
	0710- 11-231	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, SKIP, 6"	GM	1.107
	0710- 11-241	PAINTED PAVEMENT MARKINGS, STANDARD, YELLOW, 2-4 DOTTED GUIDELINE/6-10 DOTTED EXTENSION, 6"	GM	0.100
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (44101515201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	2.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	1.000
	0700- 1-600	SINGLE COLUMN GROUND SIGN ASSEMBLY, REMOVE	EA	1.000
	0705- 11- 1	DELINEATOR, FLEXIBLE TUBULAR	EA	1.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	1,373.000
	0710- 12-290	PAINTED PAVEMENT MARKINGS, DURABLE PAINT, YELLOW, ISLAND NOSE	SF	99.000
	0710- 90-	PAINTED PAVEMENT MARKINGS, FINAL SURFACE (44101515201)	LS	1.000
	0711- 11-102	THERMOPLASTIC, STANDARD, WHITE, SOLID, 8" FOR INTERCHANGE AND URBAN ISLAND	GM	0.088
	0711- 11-123	THERMOPLASTIC, STANDARD, WHITE, SOLID, 12" FOR CROSSWALK AND ROUNDABOUT	LF	2,744.000
	0711- 11-124	THERMOPLASTIC, STANDARD, WHITE, SOLID, 18" FOR DIAGONALS AND CHEVRONS	LF	103.000
	0711- 11-125	THERMOPLASTIC, STANDARD, WHITE, SOLID, 24" FOR STOP LINE AND CROSSWALK	LF	495.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.643
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	92.000
	0711- 11-224	THERMOPLASTIC, STANDARD, YELLOW, SOLID, 18" FOR DIAGONAL OR CHEVRON	LF	304.000

Call Order: 007 Proposal: E59F3

ALT	Item	Description	Unit	Quantity
	0711- 11-241	THERMOPLASTIC, STANDARD, YELLOW, 2-4 DOTTED GUIDE LINE /6-10 DOTTED EXTENSION LINE, 6"	GM	0.076
	0711- 14-125	THERMOPLASTIC, PREFORMED, WHITE, SOLID, 24" FOR CROSSWALK	LF	1,690.000
	0711- 14-160	THERMOPLASTIC, PREFORMED, WHITE, MESSAGE	EA	11.000
	0711- 14-170	THERMOPLASTIC, PREFORMED, WHITE, ARROW	EA	11.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	4.687
	0711- 16-131	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SKIP, 6",10-30 SKIP OR 3-9 LANE DROP	GM	2.978
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	3.359
	0711- 16-231	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SKIP, 6"	GM	1.114
Section 0003 Signalization				
	0633- 6-	FIBER OPTIC CABLE LOCATOR	DA	150.000
	0660- 2-102	LOOP ASSEMBLY, F&I, TYPE B	AS	29.000
	0660- 2-106	LOOP ASSEMBLY, F&I, TYPE F	AS	26.000