

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting:	05251104	Call Order: 001	Proposal: E50G0	District:05
Counties:	ORANGE			
Road Name:	US 441			
Limits:	75010000			
Project(s):	45460015201(*)	Federal Aid No:	N/A	
Total Roadway Length:	0.606 Miles	Contract Days:	100	
Total Bridge Length:	0.000 Miles	Letting Date:	11/04/25	
Total Proposal Length:	0.606 Miles	Contract Execution Days:	10	
		Special Start Date:	N/A	
		Aquis/Flexible Start Time:	30 Days	
Proposal Budget Estimate:		\$556,694.00		

Please read the full advertisement

Description:

The Improvements under this Contract consist of extending three northbound left turning lanes approximately 300 feet each on S.R. 500 (South Orange Blossom Trail) from Town Center Blvd to SR 417 South on-off ramp approximately 0.606 miles in Orange County.

PREQUALIFICATION REQUIRED

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Call Order: 001 Proposal: E50G0

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (45460015201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (45460015201)	LS	1.000
	0102- 60-	WORK ZONE SIGN	ED	2,600.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	8,000.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	200.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	228.000
	0107- 1-	LITTER REMOVAL	AC	4.800
	0107- 2-	MOWING	AC	2.270
	0110- 1- 1	CLEARING & GRUBBING (45460015201)	LS	1.000
	0110- 4- 10	REMOVAL OF EXISTING CONCRETE	SY	235.000
	0120- 1-	REGULAR EXCAVATION	CY	237.300
	0120- 6-	EMBANKMENT	CY	28.000
	0160- 4-	TYPE B STABILIZATION	SY	2,190.000
	0285-711-	OPTIONAL BASE, BASE GROUP 11	SY	1,781.000
	0334- 1- 15	SUPERPAVE ASPHALTIC CONC, TRAFFIC E	TN	220.400
	0337- 7- 88	ASPHALT CONCRETE FRICTION COURSE, TRAFFIC E, FC-12.5, PG 76-22	TN	146.900
	0520- 1- 7	CONCRETE CURB & GUTTER, TYPE E	LF	507.000
	0520- 70-	CONCRETE TRAFFIC SEPARATOR, SPECIAL- VARIABLE WIDTH	SY	263.000
	0570- 1- 2	PERFORMANCE TURF, SOD	SY	175.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (45460015201)	LS	1.000
Section 0002 Signing				
	0700- 1-111	SINGLE COLUMN GROUND SIGN ASSEMBLY, F&I GROUND MOUNT, LESS THAN 12 SF	EA	1.000
	0700- 1-500	SINGLE COLUMN GROUND SIGN ASSEMBLY, RELOCATE	EA	3.000
	0700- 13- 15	RETROREFLECTIVE SIGN STRIP- FURNISH AND INSTALL, 5'	EA	2.000
	0706- 1- 3	RAISED PAVEMENT MARKER, TYPE B	EA	58.000
	0711- 11-141	THERMOPLASTIC, STANDARD, WHITE, 2-4 DOTTED GUIDELINE/ 6-10 GAP EXTENSION, 6"	GM	0.060
	0711- 11-170	THERMOPLASTIC, STANDARD, WHITE, ARROW	EA	12.000
	0711- 16-101	THERMOPLASTIC, STANDARD-OTHER SURFACES, WHITE, SOLID, 6"	GM	0.209
	0711- 16-201	THERMOPLASTIC, STANDARD-OTHER SURFACES, YELLOW, SOLID, 6"	GM	0.188
	0711- 17- 1	THERMOPLASTIC, REMOVE EXISTING THERMOPLASTIC PAVEMENT MARKINGS- SURFACE TO REMAIN	SF	504.000